SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

JAN 2018
RECEIVED
ND OIL & GAS
DIVISION

Well File No. **90244**

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- ☐ Notice of Intent — Approximate Start Date:
- ☑ Report of Work Done — Date Work Completed: **April 5, 2017**
- ☐ Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

☐ Drilling Prognosis	☐ Spill Report
☐ Redrilling or Repair	☐ Shooting
☐ Casing or Liner	☐ Acidizing
☐ Plug Well	☐ Fracture Treatment
☐ Supplemental History	☐ Change Production Method
☐ Temporarily Abandon	☐ Reclamation
☑ Other **Annual Pressure Test - Injection Line**	

Well Name and Number					
Buck Shot SWD 5300 31-31					
Footages		Qtr-Qtr	Section	Township	Range
1717 F **S** L	**1153** F **W** L	**NWSW**	**31**	**153 N**	**100 W**
Field	Pool	County			
Baker	**Dakota**	**McKenzie**			

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s)			
Address	City	State	Zip Code

DETAILS OF WORK

Oasis Petroleum respectfully reports details of the annual pressure test of the high pressure injection line for the Buck Shot SWD 5300 31-31 (#90244):

- **Date of test: April 5, 2017**
- **Starting pressure: 1600 psi**
- **Ending pressure: 1594 psi**
- **Amount of fluid used to fill the line: 2 bbls**
- **Type of fluid used for the test: Saltwater**
- **Length of the line tested: 1.5 miles**
- **Installation date of the line: 2012**
- **Type of pipe: Flex steel**
- **Type of fittings: Stainless steel**
- **Pressure rating of the pipe and fittings: 2500 psi**

Company		Telephone Number
Oasis Petroleum North America LLC		**281-404-9513**
Address		
1001 Fannin, Suite 1500		
City	State	Zip Code
Houston	**TX**	**77002**
Signature: Caroline Hendrix	Printed Name: **Caroline Hendrix**	
Title: **Regulatory Specialist**	Date: **January 11, 2018**	
Email Address: **chendrix@oasispetroleum.com**		

FOR STATE USE ONLY

☑ Received	☐ Approved
Date: 10/5/2018	
By:	
Title: ASHLEIGH DAY UNDERGROUND INJECTION SUPERVISOR	

SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

Well File No. **90244**

RECEIVED SEP 2018 ND OIL & GAS DIVISION

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- [ ] Notice of Intent — Approximate Start Date:
- [x] Report of Work Done — Date Work Completed: **July 25, 2013**
- [ ] Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

- [ ] Drilling Prognosis
- [ ] Spill Report
- [ ] Redrilling or Repair
- [ ] Shooting
- [ ] Casing or Liner
- [ ] Acidizing
- [ ] Plug Well
- [ ] Fracture Treatment
- [ ] Supplemental History
- [ ] Change Production Method
- [ ] Temporarily Abandon
- [ ] Reclamation
- [ ] Other **Injection Start Date for SWD Well**

Well Name and Number					
BUCK SHOT SWD 5300 31-31					
Footages		Qtr-Qtr	Section	Township	Range
1717 F **S** L	**1153** F **W** L	**NWSW**	**31**	**153 N**	**100 W**
Field	Pool	County			
Baker	**Dakota**	**McKenzie**			

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s)			
Address	City	State	Zip Code

DETAILS OF WORK

Oasis Petroleum North America, LLC respectfully informs the NDIC that first injection for the subject Salt Water Disposal Well occured on July 25, 2013

Company		Telephone Number
Oasis Petroleum North America LLC		**281 404-9494**
Address		
1001 Fannin, Suite 1500		
City	State	Zip Code
Houston	**TX**	**77002**
Signature: *Sadie Goodrum*	Printed Name: **Sadie Goodrum**	
Title: **Regulatory Specialist II**	Date: **September 27, 2018**	
Email Address: **sgoodrum@oasispetroleum.com**		

FOR STATE USE ONLY

[x] Received	[ ] Approved
Date 10/4/2018	
By [signature]	
Title ASHLEIGH DAY UNDERGROUND INJECTION SUPERVISOR	

Well Integrity Report - Form 19 Summary

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840

Well File No. 90244
UIC No. W0346S0820D

Test Date: 7/30/2018 10:27:52 AM **Contractor Performing Pressure Test:** TNT
Operator: OASIS PETROLEUM NORTH AMERICA LLC **Telephone :** 2814049500
Address: 1001 FANNIN STE 1500 **City:** HOUSTON **State:** TX **Zip Code:** 77002
Well Name: BUCK SHOT SWD 5300 31-31 **Field:** BAKER
Location: **Qtr-Qtr:** NWSW **Section:** 31 **Township:** 153 **Range:** 100 **Cnty:** MCKENZIE

WELL TEST DATA

Formation: DAKOTA **Perforations:** 5589-6150 *Feet*
Tool Type: PKR **Depth:** 5522 *Feet* **Packer Model:** Arrowset 1-X
Tubing Size: 4.5 *Inches* **Tubing Type:** UNKNOWNCPVC L-80 8 RD Sesltite
Well Type: Disposal Well **Reason for Test:** UIC MIT **Test Type :** 5 Year MIT

	BEFORE TEST		START of TEST		END of TEST	
Tubing Pressure:	900 *PSIG*	Flowing	900 *PSIG*	Flowing	900 *PSIG*	Flowing
Annulus or Casing Pressure:	0 *PSIG*		1000 *PSIG*		1000 *PSIG*	

Annulus or Casing Fluid : Treated Fresh Water **Test Fluid:** Treated Fresh Water
Amount of Fluid Needed to Fill Annulus or Casing: 0.5 *Bbls*
Test Length: 15 *Minutes* **Was Annulus or Casing Bled to Zero After Test?:** Yes **If No - Pressure Left:**

INSPECTION COMMENTS

Test Result: Acceptable **Report of Work Done Required:** No

Note correction of annulus fluid to fresh water cushion

This Report is true and complete to the best of my knowledge.

Company Representative Witnessing Test: Darren Johnston **Title:** Oasis Maintenance
Commission Field Inspector Witnessing Test: Daneil Wells

NDIC Initials AWD

NORTH DAKOTA
OIL AND GAS DIVISION

Oil and Gas Division

Lynn D. Helms - Director Bruce E. Hicks - Assistant Director
Department of Mineral Resources
Lynn D. Helms - Director
North Dakota Industrial Commission
www.dmr.nd.gov/oilgas/

90244

March 20, 2017

Oasis Petroleum North America, LLC
1001 Fannin St., Suite 1500
Houston, TX 77002

RE:

Ziggy SWD 5300 32-2	BWL SWD 5201 11-3	Buck Shot SWD 5300 31-31
NESW Sec. 2-T153N-R100W	NWNW Sec. 3-T152N-R101W	NWSW Sec. 31-T153N-R100W
Williams County , Last Chance Field	McKenzie County , Camp Field	McKenzie County , Baker Field
Well File No.10945	Well File No. 90192	Well File No. 90244

To Whom It May Concern:

NDIC records indicate that injection into the above saltwater disposal well is through an injection pipeline between a pump and the well head which are not located on the same site. The NDIC requires that all offsite high pressure injection pipelines for saltwater disposal wells be tested for mechanical integrity on an annual basis. The required pipeline pressure test procedure is as follows:

1) Injection pipeline pressure test must be witnessed by an NDIC Field Inspector. Contact the appropriate NDIC Field Inspector to schedule the test.
2) **Pressure line to 100 psi above maximum injection pressure or 100 psi over the maximum operating pressure of the line whichever is greater. The duration of the pressure test must be at least 30 minutes.** Be sure to note the starting and ending pressures and the pressure at 5 minute intervals for the duration of the test.
3) Depending on the results as determined by the NDIC:
   a. It may be necessary to shut in the pressurized line for 24 hours to stabilize temperature of test fluid and allow any air or gases to accumulate in order to be purged.
   b. Following the 24 hour shut-in period, re-pressurize line and document the amount of fluid needed to return pressure to 100 psi above maximum injection pressure.
   c. Pressure test line for 30 minutes.
4) Submit to the NDIC a Form 4 Sundry Notice detailing the test results (e.g. date of test, starting and ending pressures and pressure at 5 minute intervals, amount of fluid, etc.). The Sundry Notice should also include details on the line that was tested (e.g. length of line, installation date, type of pipe, type of fittings, pressure rating of pipe and fittings, etc.).

If you have any questions, do not hesitate to contact me.

Sincerely,

Ashleigh Day
UIC Supervisor

Oil and Gas Division

Lynn D. Helms - Director Bruce E. Hicks - Assistant Director
Department of Mineral Resources
Lynn D. Helms - Director
North Dakota Industrial Commission
www.dmr.nd.gov/oilgas/

90244

May 11, 2016

RE: **Saltwater Disposal Well Reporting and Monitoring Requirements**

Dear Saltwater Disposal Operator:

This letter is to outline and clarify the Commission's requirements for monthly reporting and monitoring of saltwater disposal wells which are outlined under North Dakota Administrative Code (NDAC) Section 43-02-05-12, and the type of wastes that can be injected pursuant to the EPA guidelines for Exempt and Non-Exempt Oil and Gas Exploration and Production Wastes.

All injection into a saltwater disposal well must be measured, either through a meter or by an approved method. Accurate gauges must be placed on the tubing and tubing-casing annulus of the well for pressure monitoring. Any noncompliance with regulations or permit conditions must be reported to the Commission orally within 24 hours followed by a written explanation within 5 days.

Monthly reporting of the following information is required to be submitted for a saltwater disposal well on a Saltwater Disposal Report (Form 16):

1. Beginning and end of month meter readings.
2. Total barrels injected for the month.
3. Average daily operating injection pressure (this means a typical pressure observed while the well is injecting, not a mathematical average).
4. Sources of received fluid (these sources need to be listed by well or facility name and number, NDIC well or facility file number, and the location of each source by quarter-quarter, section, township, and range).
5. Amount of fluid received from each source.
6. Nature of the received fluid (i.e. produced water, pit water, etc.).
7. Transportation method used to transport the injection fluid to the disposal well site (i.e. pipeline or truck).

Saltwater Disposal Reports (Form 16) are due on or before the fifth day of the second month succeeding the month in which the well is capable of disposal (i.e. January report due March 5th).

Pursuant to NDAC Section 43-02-05-13.1, all records from which to make and substantiate required reports shall be kept for a period of not less than six years.

The NDIC abides by the Environmental Protection Agency guidelines for Exempt and Non-Exempt Oil and Gas Exploration and Production Wastes to determine what wastes can be accepted for disposal from oil and gas exploration and production operations. Attached is an example list of exempt and non-exempt oil and gas exploration and production wastes along with a flow chart for determining the status of a waste.

The operator is only authorized to inject Class II fluids into a saltwater disposal well. Class II fluids are generally defined as follows:

1. Produced water from oil and gas production.
2. Waste fluids from actual drilling operations.
3. Used workover, completion, and stimulation fluids recovered from production, injection, and exploratory wells.
4. Waste fluids from circulation during well cementing.
5. Pigging fluids from cleaning of collection and injection lines within the field.
6. Enhanced recovery waters including fresh water makeup and other waters containing chemicals for the purpose of enhanced recovery.
7. Gases used for enhanced recovery/pressure maintenance of production reservoirs.
8. Brine reject from water softeners associated with enhanced recovery.
9. Waste oil and fluids from clean up within the oil field.
10. Waste water from gas plants which are an integral part of production operations unless those waters are classified as hazardous waste at the time of injection.

The following fluids are non-exempt fluids and are not authorized to be injected into a Class II saltwater disposal well:

1. Unused fracturing fluids or acids.
2. Vacuum truck and drum rinsate from trucks and drums containing non-exempt waste.
3. Refined gasoline or diesel fuels.
4. Used equipment lubricating oils.
5. Refinery wastes.
6. Radioactive tracer wastes.
7. Car wash wastes.

Please distribute this letter and the attachment to the appropriate personnel responsible for reporting on and monitoring each saltwater disposal well your company operates. If you have any questions, do not hesitate to contact me.

Sincerely,

Ashleigh Day
Underground Injection Supervisor

JK/KC #10945 & #90244 & #90192 3-29-16

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Michael Kukuk
sis Petroleum North America LLC
1001 Fannin Suite 1500
Houston, TX 77002

2. Article Number (Transfer from service label) 7013 2630 0001 2309 9846

COMPLETE THIS SECTION ON DELIVERY

A. Signature X ☐ Agent ☐ Addressee

B. Received by (Printed Name)

C. Date of Delivery 4-7-16

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

Received
APR 11 2016
ND Oil & Gas Division

3. Service Type
☑ Certified Mail® ☐ Priority Mail Express™
☐ Registered ☐ Return Receipt for Merchandise
☐ Insured Mail ☐ Collect on Delivery

4. Restricted Delivery? (Extra Fee) ☐ Yes

PS Form 3811, July 2013 Domestic Return Receipt

NORTH DAKOTA
OIL AND GAS DIVISION

Oil and Gas Division

Lynn D. Helms - Director Bruce E. Hicks - Assistant Director

Department of Mineral Resources

Lynn D. Helms - Director

North Dakota Industrial Commission

www.dmr.nd.gov/oilgas

March 29, 2016

Michael Kukuk
Oasis Petroleum North America LLC
1001 Fannin Suite 1500
Houston, TX 77002

RE: Buck Shot SWD 5300 31-31
NWSW Section 31-T153N-R100W
McKenzie County, ND
Baker Field
Well File No. 90244

Dear Mr. Kukuk:

NDIC records indicate that injection into the above saltwater disposal well is through a pipeline from the offsite tank battery located in the SW/4 of Section 4, Township 152 North, Range 101 West, approximately 1.5 miles northeast to the Buck Shot SWD 5300 31-31 (NDIC file no. 90244) well. The permit for fluid injection issued September 5, 2012 requires this offsite high pressure injection pipeline be mechanical integrity tested on an annual basis. The required pipeline pressure test procedure is as follows:

1) Injection pipeline pressure test must be witnessed by an NDIC Field Inspector. Contact the appropriate NDIC Field Inspector to schedule the test.
2) The entire duration of the pressure test must be recorded on a chart recorder.
3) **Pressure line to 100 psi. above the permitted maximum injection pressure and test for 30 minutes**. Be sure to note the starting and ending pressures.
4) Depending on the results as determined by the NDIC:
   a. It may be necessary to shut in the pressurized line for 24 hours to stabilize temperature of test fluid and allow any air or gases to accumulate in order to be purged.
   b. Following the 24 hour shut-in period, re-pressurize line and document the amount of fluid needed to return pressure to 100 psi. above the permitted maximum injection pressure.
   c. Pressure Test line for 30 minutes.
5) Submit to the NDIC a Form 4 Sundry Notice detailing the test results (e.g. date of test, starting and ending pressures, amount of fluid, etc.). Be sure to include as an attachment to the Sundry Notice the pressure recorded data (i.e. a copy of the chart) of the entire procedure.

Please proceed diligently to perform this test by May 2, 2016. If you have any questions, do not hesitate to contact me.

Sincerely,

Kevin Connors
Pipeline Program Supervisor

Certified Mail: 7013 2630 0001 2309 9846

WELL COMPLETION OR RECOMPLETION REPORT - FORM 6

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 2468 (04-2010)

Well File No. 90244

DEC 2013 RECEIVED ND OIL & GAS DIVISION

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

Designate Type of Completion

☑ Oil Well ☐ EOR Well ☐ Recompletion ☐ Deepened Well ☐ Added Horizontal Leg ☐ Extended Horizontal Leg
☐ Gas Well ☑ SWD Well ☐ Water Supply Well ☐ Other:

Well Name and Number: BUCK SHOT SWD 5300 31-31	Spacing Unit Description: SEC 31 T153N R100W
Operator: Oasis Petroleum North America LLC; Telephone Number: (281) 404-9500	Field: Baker
Address: 1001 Fannin, Suite 1500	Pool: Dakota Group
City: Houston; State: TX; Zip Code: 77002	Permit Type: ☑ Wildcat ☐ Development ☐ Extension

LOCATION OF WELL

At Surface		Qtr-Qtr	Section	Township	Range	County
~~1740~~ 17 F S L	~~1125~~ 53 F W L	~~NWSE~~ SW	31	153 N	100 W	MCKENZIE

Spud Date	Date TD Reached	Drilling Contractor and Rig Number	KB Elevation (Ft)	Graded Elevation (Ft)
June 17, 2013	June 22, 2013	Precision 565	2182	2157

Type of Electric and Other Logs Run (See Instructions)

CASING & TUBULARS RECORD (Report all strings set in well)

Well Bore	String Type	String Size (Inch)	Top Set (MD Ft)	Depth Set (MD Ft)	Hole Size (Inch)	Weight (Lbs/Ft)	Anchor Set (MD Ft)	Packer Set (MD Ft)	Sacks Cement	Top of Cement
Surface Hole	Surface	9 5/8		2200	12 1/2	36				0
Vertical Hole	Intermediate	7		6191	8 3/4	26			508	2350

PERFORATION & OPEN HOLE INTERVALS

Well Bore	Well Bore TD Drillers Depth (MD Ft)	Completion Type	Open Hole/Perforated Interval (MD,Ft) Top	Bottom	Kick-off Point (MD Ft)	Top of Casing Window (MD Ft)	Date Perf'd or Drilled	Date Isolated	Isolation Method	Sacks Cement
Vertical Hole	6555	Other	5589	6150	4600		07/20/2013			

PRODUCTION

Current Producing Open Hole or Perforated Interval(s), This Completion, Top and Bottom, (MD Ft)	Name of Zone (If Different from Pool Name)

Date Well Completed (SEE INSTRUCTIONS)	Producing Method	Pumping-Size & Type of Pump	Well Status (Producing or Shut-In)
July 23, 2013			

Date of Test	Hours Tested	Choke Size	Production for Test	Oil (Bbls)	Gas (MCF)	Water (Bbls)	Oil Gravity-API (Corr.)	Disposition of Gas
		/64					°	

Flowing Tubing Pressure (PSI)	Flowing Casing Pressure (PSI)	Calculated 24-Hour Rate	Oil (Bbls)	Gas (MCF)	Water (Bbls)	Gas-Oil Ratio

GEOLOGICAL MARKERS

Formation	MD (Ft)	TVD (Ft)

PLUG BACK INFORMATION

Well Bore	Type of Plug	Top (Ft)	Bottom (Ft)	Sacks Cement

CORES CUT

Top (Ft)	Bottom (Ft)	Formation	Top (Ft)	Bottom (Ft)	Formation

Drill Stem Test

Test Date	Formation	Top (Ft)	Bottom (Ft)	BH Temp (°F)	CL ppm	H2S ppm	Shut-in 1 (PSIG)	Shut-in 2 (PSIG)

Drill Pipe Recovery

Sample Chamber Recovery

Test Date	Formation	Top (Ft)	Bottom (Ft)	BH Temp (°F)	CL ppm	H2S ppm	Shut-in 1 (PSIG)	Shut-in 2 (PSIG)

Drill Pipe Recovery

Sample Chamber Recovery

Test Date	Formation	Top (Ft)	Bottom (Ft)	BH Temp (°F)	CL ppm	H2S ppm	Shut-in 1 (PSIG)	Shut-in 2 (PSIG)
	cmt							

Drill Pipe Recovery

Sample Chamber Recovery

Test Date	Formation	Top (Ft)	Bottom (Ft)	BH Temp (°F)	CL ppm	H2S ppm	Shut-in 1 (PSIG)	Shut-in 2 (PSIG)

Drill Pipe Recovery

Sample Chamber Recovery

Test Date	Formation	Top (Ft)	Bottom (Ft)	BH Temp (°F)	CL ppm	H2S ppm	Shut-in 1 (PSIG)	Shut-in 2 (PSIG)

Drill Pipe Recovery

Sample Chamber Recovery

Well Specific Stimulations

Date Stimulated	Stimulated Formation	Top (Ft)	Bottom (Ft)	Stimulation Stages	Volume	Volume Units
07/20/2013	Dakota	5625	6150	8	9000	Gallons

Type Treatment	Acid %	Lbs Proppant	Maximum Treatment Pressure (PSI)	Maximum Treatment Rate (BBLS/Min)
Acid	100			

Details

Date Stimulated	Stimulated Formation	Top (Ft)	Bottom (Ft)	Stimulation Stages	Volume	Volume Units

Type Treatment	Acid %	Lbs Proppant	Maximum Treatment Pressure (PSI)	Maximum Treatment Rate (BBLS/Min)

Details

Date Stimulated	Stimulated Formation	Top (Ft)	Bottom (Ft)	Stimulation Stages	Volume	Volume Units

Type Treatment	Acid %	Lbs Proppant	Maximum Treatment Pressure (PSI)	Maximum Treatment Rate (BBLS/Min)

Details

Date Stimulated	Stimulated Formation	Top (Ft)	Bottom (Ft)	Stimulation Stages	Volume	Volume Units

Type Treatment	Acid %	Lbs Proppant	Maximum Treatment Pressure (PSI)	Maximum Treatment Rate (BBLS/Min)

Details

Date Stimulated	Stimulated Formation	Top (Ft)	Bottom (Ft)	Stimulation Stages	Volume	Volume Units

Type Treatment	Acid %	Lbs Proppant	Maximum Treatment Pressure (PSI)	Maximum Treatment Rate (BBLS/Min)

Details

ADDITIONAL INFORMATION AND/OR LIST OF ATTACHMENTS

Tubing: 4.5 in. Seal Tite CPVC L-80 8 RD w/ Inserts set @5469

Packer: 7 in. Arrowset 1-X Packer set @5521

CIBP set @6190 isolated open hole 6191-6555

I hereby swear or affirm that the information provided is true, complete and correct as determined from all available records.	Email Address ccovington@oasispetroleum.com		Date 11/19/2013
Signature Chelsea Covington	Printed Name Chelsea Covington	Title Regulatory Assistant	

Well Integrity Report - Form 19 Summary

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840

Well File No. 90244
UIC No. W0346S0820D

Test Date: 7/24/2013 9:52:24 AM **Contractor Performing Pressure Test:** Black Hawk Energy Services Rig 310
Operator: OASIS PETROLEUM NORTH AMERICA LLC **Telephone :** 2814049500
Address: 1001 FANNIN STE 1500 **City:** HOUSTON **State:** TX **Zip Code:** 77002
Well Name: BUCK SHOT SWD 5300 31-31 **Field:** BAKER
Location: **Qtr-Qtr:** NWSW **Section:** 31 **Township:** 153 **Range:** 100 **Cnty:** MCKENZIE

WELL TEST DATA

Formation: DAKOTA **Perforations:** 5589-6150 *Feet*
Tool Type: PKR **Depth:** 5522 *Feet* **Packer Model:** Arrowset IX
Tubing Size: 4.5 *Inches* **Tubing Type:** CPVC L-80 8 RD Sesltite
Well Type: Disposal Well **Reason for Test:** UIC MIT **Test Type :** Initial MIT

	BEFORE TEST	START of TEST	END of TEST
Tubing Pressure:	0 *PSIG* Shut In	0 *PSIG* Shut In	0 *PSIG* Shut In
Annulus or Casing Pressure:	0 *PSIG*	1000 *PSIG*	1000 *PSIG*

Annulus or Casing Fluid : Treated Salt Water **Test Fluid:** Treated Salt Water
Amount of Fluid Needed to Fill Annulus or Casing: 0 *Bbls*
Test Length: 15 *Minutes* **Was Annulus or Casing Bled to Zero After Test?:** Yes **If No - Pressure Left:**

INSPECTION COMMENTS

Test Result: Acceptable **Report of Work Done Required:** Yes

SUBMIT FORM 6 COMPLETION REPORT.
SUBMIT FORM 4 NOTING DATE OF FIRST INJECTION WHEN APPLICABLE (SJF)

This Report is true and complete to the best of my knowledge.

Company Representative Witnessing Test: Adam Clifford **Title:** Consultant
Commission Field Inspector Witnessing Test: Richard Ryan

NDIC Initials SJF

SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

1234567891011121314151617181920212223242526272829303
JUL 2013
RECEIVED
ND OIL & GAS
DIVISION

Well File No.
90244

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- [x] Notice of Intent — Approximate Start Date: **July 5, 2013**
- [ ] Report of Work Done — Date Work Completed:
- [ ] Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

- [ ] Drilling Prognosis
- [ ] Redrilling or Repair
- [ ] Casing or Liner
- [ ] Plug Well
- [ ] Supplemental History
- [ ] Temporarily Abandon
- [x] Other: **Intent to reclaim reserve pit**
- [ ] Spill Report
- [ ] Shooting
- [ ] Acidizing
- [ ] Fracture Treatment
- [ ] Change Production Method
- [x] Reclamation

Well Name and Number					
Buck Shot SWD 5300 31-31					
Footages		Qtr-Qtr	Section	Township	Range
1717 F **S** L	**1153** F **W** L	**NWSW**	**21**	**153 N**	**100 W**
Field	Pool		County		
Baker	**Dakota Group**		**McKenzie**		

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s)			
Neu Construction			
Address	City	State	Zip Code
204 S. Ellery Avenue P.O. Box 461	**Fairview**	**MT**	**59221**

DETAILS OF WORK

Oasis Petroleum North America LLC plans to reclaim the reserve pit for the above referenced wells as follows:
The NDIC field inspector, Rick Dunn and the surface owners, were notified on 07/03/2013.
Surface owners: Wes Lindvig 14075 41st Street NW Alexander, ND 58831
Spread material out in pit, cut top edge of liner and fold cuttings, cover entire pit with liner, backfill with clay slope and contour wellsite to ensure proper drainage.

Company		Telephone Number
Oasis Petroleum North America LLC		**281-404-9591**
Address		
1001 Fannin, Suite 1500		
City	State	Zip Code
Houston	**TX**	**77002**
Signature: Chelsea Covington	Printed Name: **Chelsea Covington**	
Title: **Regulatory Assistant**	Date: **July 3, 2013**	
Email Address: **Ccovington@oasispetroleum.com**		

FOR STATE USE ONLY

[ ] Received	[x] Approved
Date	7-8-13
By	[signature]
Title	[signature]

Oasis Petroleum North America LLC.

Buck Shot SWD 5300 31-31H



Services Performed For:

Mike Box, Andy Nelson

Oasis Petroleum North America LLC.

1001 Fannin, Suite 1500

Houston , TX 77002

Onsite Geology Performed by:

Tyson Zentz, Adam Graves

RPM Consukting

geology@rpm-inc.org

(406) 259-4124

Well Evaluation

Oasis Petroleum North America LLC.

Buck Shot SWD 5300 31-31H

NW SW Sec. 31, T153N-R100W

McKenzie County, North Dakota

Precision 565 drilling Oasis Petroleum Buck Shot SWD 5300 31-31H July 1st, 2013

Synopsis

Oasis Petroleum - *Buck Shot SWD 5300 31-31H* [NW SW Sec. 31, T153N-R100W] is located approximately 13 miles south of Williston, North Dakota situated in the Indian hills prospect area. Buck Shot SWD 5300 31-31H is a proposed injection well with a single extended lateral leg trending 14.2 degrees from the NW SW corner of section 31 to the SW NW corner of section 31. The intended targeted reservoir is the upper zone of the Inyan Kara formation of the Dakota.

Control Wells

Throughout the course of drilling the *Buck Shot SWD 5300 31-31H* well one primary offset well provided valuable data in regards to formation tops, lithology and geosteering decisions. There were five offset wells total, but the *Lewis Federal 5300* was the only offset used due to the extensive similarities with the *Buck Shot SWD 5300 31-31H* well. The estimated prognosis formation tops were provided by Oasis Petroleum prospect geologists. Correlating this data with this offset well provided a generalized structure map for the *Buck Shot* well. This data was used to further estimate the distance to the target while landing the curve (See Table 1)

The primary control well, the *Lewis Federal 5300* [NW SW Sec. 31 T153N R100W] was congruently used to establish structural relationship to the northeast the Lewis well is operated by Oasis Petroleum North America LLC and was completed in the Dakota formation. The neutron-density/gamma ray log was used to correlate the drilling of the *Buck Shot SWD 5300 31-31H*.



Table 1) Displaying control well formation tops, estimated distance to target isopach and isopach thickness.

Geologic Assessment

Methods

RPM Geologic provided wellsite geologic supervision for *Buck Shot SWD 5300 31-31H* with a team of geologic consultants. Sample logging and geo-steering services were conducted by a 2 person geology team throughout the vertical and lateral hole. Lagged lithology samples were collected by rig personnel at 30' intervals as directed by the wellsite geologist. Additional samples were collected at intervals of greater interest.

Wet and dry sample analysis was conducted under a 10x-75x zoom digital stereoscope. Comprehensive lithology descriptions were recorded on the vertical, horizontal logs and as an appendix to this report. Chemical testing of samples using 10% HCl solution aided in accurately deducing mineral composition. Additionally one set of dried, cleaned samples were retained for the North Dakota Industrial Commission.

RPM geologists used lithology, gamma ray, rates of penetration, and natural formation deflections to advise directional and company personnel on TVD targets and geosteering decisions with the goal of maintaining a predetermined drilling interval with the target formation. Consultation with Oasis Petroleum Operations geologists provided structural maps, cross sectional interpretations and estimated formation tops prognosis.

Vertical Operations

Overview

The *Buck Shot SWD 5300 31-31H* was spud by Precision 565 on June 18th, 2013 with a 13 1/2" surface hole drilled to 2,135'. 9 5/8" J-55 LTC 36# surface casing was set and cemented to a total depth of 2,135' and drilling resumed with BHA #2 (Bottom hole assembly) consisting of an 8 ¾" Smith MDSIZ616. After setting surface casing the fresh water mud was displaced with diesel invert oil based mud for the remainder of the vertical and curve. A total depth of 6,035' was reached in the vertical, and at this point a cement plug was pumped to set up for the drilling of the 70 degree tangent. After pumping cement the well took on water below the forth sand bed, and due to this new cement plug was set to a depth of 5,255' MD

RPM Geologists began logging of the *Buck Shot SWD 5300 31-31H well* in the Pierre formation per client specifications.

Lithology

Logging of the Pierre Shale began at 4,000' MD.

The Pierre Shale [Montana Group] was logged from 4,000' MD / 4,000' TVD. Samples descriptions are as follows (Figure 1);

> SHALE: light to medium gray, occasional orange, soft to friable, sub-blocky to blocky, earthy texture, no visible porosity
>
> SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, no visible porosity



Figure 1) Pierre Shale taken from 6,360' MD. (45x zoom wet)

Directional Operations

Directional services were provided by RPM Consulting while MWD services were provided Ryan energy. RPM Geologists worked closely and efficiently with directional and MWD Services to effectively maintain the wellbore within the target zone.

Curve

Drilling of the curve began on the 27th June 2013 with BHA #3 consisting of an 8.75" Smith XR+. The curve was completed to a depth of 6,207' MD in 25 hours, with an average rate of penetration of 38.08 ft. /hr. Intermediate casing (7" 26# L-80 LTC) was successfully set to a total depth of 2,135' and cemented back to surface. 4.5" PVC-lined tubing packer set was then set to a depth of 6,202' MD and cemented back.

Initially target landing depths were incorporated from the geologic prognosis formulated previous to drilling operations. Once the curve commenced amendments to the landing target and the proposed top of the Forth Dakota Sand were made based on gamma ray interpretations of "marker beds". The first of these adjustments was made at the Greenhorn, no change here was necessitated. The second consistent "marker bed" was the

Second Dakota Sand Top; an adjustment from the initial TVD of the top of the Third Dakota Sand Top was made based on the gamma ray interpretation. No other adjustments were made and the curve was successfully landed at a measured depth of 6,202'.

Lithology

The Greenhorn [Colorado Group] is the first "marker bed" used to estimate the isopach depth to the target zone. Drilled at 4,644' MD / 4,644' TVD (-2,462' MSL) was 5' low to the prognosis. Sample descriptions from the Greenhorn are as follows (*Figure 2*);

> SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

> SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, slightly calcareous, earthy texture, clay in part, no visible porosity

> SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, clay in part, no visible porosity



Figure 2) The Greenhorn marker bed sample showing medium to dark grey calcareous shale. 4,700' MD (45x zoom wet)

The Mowry [Dakota Group] drilled at 5,060' MD / 5,052' TVD (-2,875 MSL) 3' low to the prognosis depth. Samples are described as follows (*Figure 3*);

SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, clay in part, no visible porosity

SANDSTONE: light gray, white, trace light brown, firm to friable, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity

SLTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, clay in part, no visible porosity



Figure 3) The Mowry shale and siltstone from 5,500' MD (45x zoom wet)

The Dakota Top [Dakota Group] was drilled at 5,518 MD / 5,471' TVD (-3,289' MSL) 1' high to the prognosis depth. Samples are described as follows;

SLTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, clay in part, no visible porosity

The <u>First Dakota Sand Top</u> [Dakota Group] was drilled at 5,588' MD / 5,522' TVD (-3,340 MSL) 4' high to the prognosis depth. Samples are described as follows (*Figure 4*);

> SLTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, clay in part, no visible porosity



Figure 4) First Dakota Sand Top-Second Dakota Sand Base taken from 5,860 MD (45x zoom wet)

The <u>First Dakota Sand Base</u> [Dakota Group] was drilled at 5,631' MD / 5,553' TVD (-3,371 MSL) 6' high to the prognosis depth. Samples are described as follows (*Figure 4*);

> SLTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, clay in part, no visible porosity

The Second Dakota Sand Top [Dakota Group] was drilled at 5,864' MD / 5,666' TVD (-3,484 MSL) 14' high to the prognosis depth. Samples are described as follows (*Figure 4*);

> SLTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub-blocky to blocky, earthy texture, clay in part, no visible porosity
>
> SLTY SANDSTONE: light brown to brown, firm to friable, fine grained, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity

The Second Dakota Sand Base [Dakota Group] was drilled at 6,154' MD / 5,763' TVD (-3,573 MSL) 4' high to the prognosis depth. Samples are described as follows (*Figure 4*);

> SLTY SANDSTONE: light grey to grey, trace brown firm to friable, fine grained, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity

Lateral

Lateral operations began on 30th of June 2013 with bit #4, a 6" Varel PDC. Diesel invert oil based mud was displaced with saltwater brine for the remainder of the hole. The assembly was pulled from the hole due to mud motor failure.

Bit #4, a 6" Varel PDC , drilled 348' in 6 hrs at an average rate of penetration of 58 ft/hr. Proposed total depth was reached at 10:45 am on 1st July 2013. The *Buck Shot SWD 5300 31-31H well* was drilled to a total depth of 6,555' MD. The bottom hole location using a projected to bit survey is as follows: 1,096.59' N & 297.73' E of surface location 2,806.59' FNL & 11,422.73' FWL, NW SW Sec. 31, T153N, R100W, Mckenzie County, North Dakota.

Lithology

The Third Dakota Sand Top [Dakota Group] was drilled at 6,264' MD/ 5,800' TVD (-3,617 MSL) 5' high to the prognosis depth. Samples are described as follows (*Figure 5*);

> SLTY SANDSTONE: light grey to grey, trace brown firm to friable, fine grained, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible intergranular porosity



Figure 5) Third Dakota Sand Bench taken from 6,280' MD (45x zoom wet)

The Third Dakota Sand Base [Dakota Group] was drilled at 6,301' MD / 5,816' TVD (-3,630 MSL) 9' high to the prognosis depth. Samples are described as follows (*Figure 5*);

> SLTY SANDSTONE: light grey to grey, trace brown firm to friable, fine grained, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible inter granular porosity.

The Forth Dakota Sand Top [Dakota Group] was drilled at 6,480' MD / 5,854' TVD (-3,678 MSL) 7' low to the prognosis depth. Samples are described as follows (*Figure 6*);

> SLTY SANDSTONE: light grey to grey, trace brown firm to friable, fine grained, sub-rounded to sub-angular, calcareous cemented, quartz in part, possible inter granular porosity



Figure 6) Forth Dakota Sand Top showing clean low gamma sand. (75x zoom wet)

Geosteering

The target zone was initially defined only as the 10' below the Forth Dakota Sand Top, however a TD of 6,555' MD, 5,900' TVD was agreed on. A proposed tangent of 60 to 70 degrees was plotted initially when drilling out of the surface casing shoe. This dip was amended as repetitious markers were observed while drilling the lateral.

Summary

1) The *Buck Shot SWD 5300 31-31H* well was spud by Precision 565 on the 18th of June, 2013 as a proposed water injection well in the Indian Hills of McKenzie County, North Dakota

2) A mud program consisted of diesel invert (9.6 – 12.5 ppg) was utilized to drill the vertical and curve build section. The mud program was then switch to Saltwater brine for the lateral.

3) Four bits were utilized to drill the well to TD: 1 for surface, 1 for the vertical, 1 for the curve & 1 for the lateral.

4) The lateral targeted the upper part of the Forth Dakota Sand Bench. Approximately 10' TVD down from the top of the bench.

5) Proposed total depth was reached at 10:45 am on 1st of July 2013. The Buck Shot SWD 5300 31-31H well was drilled to a total depth of 6,555'.

6) The bottom hole location using a projected to bit survey is as follows; 1,096.59' N & 297.73' E of surface location 2,806.59' FNL & 1,422.73' FWL, SW NW Sec. 31 T153N, R100W, Divide County, North Dakota.

7) The *Buck Shot SWD 5300 31-31H* is currently awaiting completion.

Composed and submitted by,

Tyson Zentz
Wellsite Geologist
RPM Geologic

Well Information

Operator:	*Oasis Petroleum North America LLC*	**API #:**	*33-053-90244*
Address:	*1001 Fannin Suite 1500* *Houston, TX 77002*	**ND Well File #:**	*90244*
		Surface Location:	*NW SW SEC. 31, T153N, R100W*
Well Name:	***Buck Shot SWD 5300 31-31H***	**Footages:**	*1,710' FSL & 1,125' FWL*
Field/ Prospect:	*Indian Hills*	**County, State:**	*McKenzie Co., North Dakota*
Elevation:	*GL: 2,157* *KB: 2,152'*	**Basin:**	*Williston*
Spud Date:	*18-Jun-13*	**Well Type:**	*Salt Water Disposal*

Contractor:	*Precision 565*	**Chemical Company**	*NOV*
Toolpushers:	*Brian Blackledge*	**Mud Engineer**	*Will McCallister*
Field Supervisors:	*Elijah Puckett, Chris Gorder*	**H_2S MONITORING:**	
Directional Drilling	*RPM Consulting Inc.*	**MWD**	*Ryan Energy* Edgar Maldonado, Eroms Omonzejele

Wellsite Geologist	*Tyson Zentz* *Adam Graves*	**Rock Sampling:**	*30' from 4,000' to 6,555'*
Prospect Geologist	*Mike Box*	**Gas Detector**	
Sample Examination:	Binocular microscope & fluoroscope	**Sample Cuts:**	*N/A*
Horizontal Target	*Dakota*		

Key Offset Wells: **Lewis Federal 5300 31-31H**

Pumps:	#1 & #2: Rostel Triplex - 12" Stroke length Output: 0.0838 bbl/stk		
Mud Type:	*Diesel invert mud 2,235 - 6,035'; Saltwater Brine from 6,202'-6,555'*		
Casing:	*Surface: 9 5/8" 35# J-55 LTC @ 2,135' MD* *Intermediate: 7" 26# L-80 LTC @ 6,202' MD*		
Hole Size:	*13 1/2" from conductor pipe at 90' to 2,135' MD*	*8 3/4" to 6,202' MD*	*6" to 6,555' TD*
Total Drilling Days:	*14 days*		

Horizontal Target:	*Dakota*	**BOTTOM HOLE LOCATION:**	1096.59' N & 297.73' E of surface location 2,806.59' FNL & 1,422.73 FWL SE SW Sec. 31 T153N, R100E
Kick-Off Point / Date:	*6,202' 7/1/2013*		
Total Depth/ Date:	*6,555' at 10:45 am on July 1 2013*		
Ending Vertical Section	1,136.13		
Ending Azimuth	16.7		
Status of Well:	Awaiting Completion		
Exposure to Formation:	100%		

Daily Activity

Day	Date 2013	Depth 0600 Hrs	24 Hr Footage	Bit #	WOB (Klbs)Rotate	WOB (Klbs) Slide	RPM (RT)	Pump Pressure	SPM 1	SPM 2	GPM	24 Hr Activity	Formation
1	6/18	2,235'	0'	-	-	-	-	-	-	-	-	Install monkey board camera, catwalk camera, doghouse camera and mud tank camera, install new water lines and valves, set and function test crown saver, draw works, wait on parts for MCWS, function mudpumps, install spacer spool on BOP stack, install ckoke line, weatherford wellhead, quick conn., nipple up BOPS, install rot head, R/U koomey lines to BOP stack/function test BOP, changed out upper and lower pipe rams, R/U orbit valve C/O saver sub, R/U kill line and torque all bolts, Nipple up BOP	Pierre
2	6/19	2,235'	0'	1	-	-	-	-	-	-	-	Tighten choke line t/stack, open upper and lower pipe ram doors change out ring gasket, realign flow line and attach t/orbit valve, test choke manifold 250 psi low-5000 psi, test TIW valve, dart valve, lower pipe rams, HCR 250 psi low-5000 psi high, test annulars 250 psi low-2500 psi high, install test plug in rotate head and test rot head (failed), test rot head 1500 psi/test 5' TIW, dart valve-250 psi low 5000 psi high, VBR lower, 5' upper pipe rams, inside kill, annular accumulator function test, test CSG-1500 psi, set wear bushing and install trip nipple, s/m p/u BHA, p/u 6.5" drill collars and 5" HWDP, p/u 5" dp	Pierre
3	6/20	5,531'	3,296'	1	15	-	65	2950	70	70	586	RIH w/5 DP T/2126', remove trip nipple and install rotate rubber, fill pipe, break circ, press. test surface equipment w/rig pumps t/1000 psi, funct. test drilling choke,drilling through float equipment and shoe t/2250', new hole t/2250' shoe set at 2225', perform fit t/250 psi, 12.5 EMW, drill f/2250'-5172', circ and c/o low psi rot head for high psi rot head, drill 5172'-5531', survey and connections, rig service	Dakota
4	6/21	6,035'	504'	1	22	-	45	1700	90	0	317	drilling f/5531'-5978', shut in well, monitor and record sicp, sicp 200 psi, open well, kick on pumps t/drilling rate and close choke holding 200 psi on casing, drilling f/5978'-6035', circ b/u thru the choke while working pipe, POOH f/6035'-5441' tripping out with 200 psi on casing, TIH f/5441'-5794', circ b/u thru the choke while weighting up mud system holding 150 psi on the casing, circ through choke/building kill mud, pump kill mud through choke, pump slug, flow check, POOH f/5780'-4340', C/O high pressure rot head or trip nipple, cont POOH f/4340-BHA (collars), L/D drill collars	Dakota
5	6/22	6,035'	0'		-	-	-	-	-	-	-	LO/ 6.5" DC and dir tools, PJSM w/Schlumberger and rig crew, R/U wireline unit and equip, RIH, L/O triple combo, R/D wireline equipment, lube traveling block, topdrive and draw works, P/U andRIH w/24 joints of 2 7/8 tubing, move 10 stands 5" HWDP, t/ drillers side in derrick, TIH f/cement assembly t/5017', P/U 7 joints 5" DP, circ bottoms up/pump lcm pill, S/M and R/U schlumberger, pump cement plug, POOH 7 stands and single to get out from cement, circ bottoms, pump 2nd cement plug, POOH 11 stands to get out of cement, circ bottoms up, rig service	Dakota
6	6/23	4,818'	-1,217'	2	-	2	45	1050	80	0	282	circ bottoms ups and pump slug, POOH f/5345'-745', break and L/O X-O subs, L/O 2 7/8" tubing, R/D elevators bales and hanger, P/U and M/U 8.75" button bit, 2 X-O subs ans RIH with 10 stands HWDP t/950', P/U and M/U 30 joints 5" HWDP f/pipe rack, TIH with 5" dp t/4364', circ B/U, mousehole 1 stand 5" dp and M/U t/1 stand 5" dp, tag cement plug at 4389', drilling thru cement f/4389'-4456', circ B/U, wash and reaming (looking to tag cement), circ B/U, pull 5 stands, circulate waiting on cement to cure, TIH 5 stands, wash and ream, rig service, circ waiting on cement	Greenhorn

7	6/24	4,992'	174'	2	-	5	25	835	0	93	327	circ while waiting on new hydraulic press block for draw works, drilling thru cement plug f/4814'-4904', circ while trouble shooting topdrive, drilling thru cement plug f/4904'-4994', circ B/U while working pipe, shut in well, check monitor SICP, circ weight up mud in system f/10.6 ppg t/10.8ppg, flow check pump slug POOH f/4992'-4902', POOH t/bit L/D bit, s/m add extension and r/u tubing elevators, P/U cement shoe and 21 joints 2 7/8" tubing, TIH f/2 7/8" tubing t/1933'	Greenhorn
8	6/25	4,992'	0'	2	-	-	-	575	81	0	285	TIH f/1933'-4980' w/5" dp, flow check, circ B/U, SM with schlumberger and rig crew, R/U chictan and pum in sub, pump 21 bbls, POOH f/4980'-3904', circ B/U, build and pump slug, POOH f/3904'-674', L/O 2 7/8" tubing f/674'-356', L/D 2 7/8 tubing, flow check R/D tubing elevators, bales extension L/D slips clean rig floor, rig service, P/U bit, bit sub and TIH t/3,918' wash down 1 stand, circ B/U, wash and ream f/3918'-4413', tag cement at 4413', pull 5 stands, circ waiting on cement to cure	Greenhorn
9	6/26	4,663'	-329'	2	30	8	35	1720	100	0	351	circ waiting on cement to cure, TIH with 3 stands 5" dp f/4098'-4366', wash down t/4400', circ B/U, build and pump slug, POOH f/4450'-surface, L/O bit and bit sub, P/U bit, P/U and M/U mud motor, M/U bit t/motor, P/U and M/U UBHO sub and monel, scribe and orientate, PU and M/U 1 joint monel, TIH t/2122', perform shallow hole test on MWD tool, cont TIH f/2122-4363, remove trip nipple and install rotate rubber, wash down f/4363'-4050', dir drilling f/4450'-4663', grease blocks, top drive and draw works	Greenhorn
10	6/27	5,304'	641'	3	37	38	36	2160	0	112	394	drilling f/4663'-4950', slide f/4950'-5050', drilling f/5050'-5214', slide f/5214'-5255', circ and build slug at 5255', POOH f/5255'-91', lay down bit and mud motor, remove MWD tool, make up new bit and motor, install MWD tool and scribe, TIH f/91'-5255' washing down last 90', dir drilling f/5255'-5,304'	Mowry
11	6/28	5,956'	652'	3	28	43	25	2030	0	112	394	Drill/slide f/5304'-5632', lube rig grease blocks, top drive, and drawworks, dir drilling f/5632'-5956', grease blocks, top drive and swivel packing	Dakota
12	6/29	6,207'	251'	3	28	43	25	2030	0	112	394	Drill/slide f5956'-6207', POOH for short trip t/4631', TIH f4631'-6207', circ B/U, flow check, POOH f/6207'-5527', POOH and strap f/5527'-91', lay down BHA, pull wear bushing, rig up casing crew, make up shoe and float collar, run casing f/surface-4543', rig up bell extensions and crt, grease draw works, blocks and top drive	Dakota
13	6/30	6,207'	0'	-	-	-	-	800	70	0	246	R/U crt tool/run 7" casing f/4543'-6202', circ thru casing B/U, troubleshoot drawworks, wire shorted in ads box, R/U cmt head/test lines t/5000 psi, cement 7" casing, R/D cmt head and lines/pulled landd JT, cut drill line, slip/cut 100' drill cable, lay down casing elevators and bell extensions, R/U 5" elevators and laydown 58 stands of dp and 20 stands 5" HWDP in mouse hole, service iron rough neck, grease draw works, continue laying down dp, run in 7" pack off stack, could not get pack off to run down stack while screwed into top drive, unscrewed and set pack off with drill pipe elevators and put 10K on packoff to ensure is set, pressure test for 15 mins and remove retrieval tool	Dakota
14	7/1	6,293'	86'	4	5	-	45	1400	75	0	264	Change saver sub to XT-29, make up mud motor, 2 monels, install MWD tool and make up bit, grease blocks, top drive and swivel packing, run 4" dp in hole f/surface-4675', motor on lube pump for draw works bad, change out motor on lube, pump for drawworks, continue to work on changing out motor for lube pump, rotation on motor was good and pump works, continue running 4" dp in hole f/4675'-6293'	Dakota

Bit Record

Bit #	Size	Make	Model	Serial #	Jets	Depth In	Depth Out	Footage	Hours	Mean ROP (ft/hr)	Accum. Hours
1	8 3/4	Smith	MDSIZ616	JG7119	6x20	2,225'	6,035'	3,810'	26	146.54	26.0
2	8 3/4	Smith	XRT	PY6169	6x22	4,450'	5,255'	805'	14	57.50	40.00
3	8 3/4	Smith	XR+	PY3548	1x16 3x22	5,255'	6,207'	952'	25	38.08	65.00
4	6	Varel	PDC	4005	3x18 3x20	6,207'	6,555'	348'	6	58.00	71.00

Daily Mud Data

Day	Date 2013	Depth (0600 Hrs)	Mud WT (ppg)	VIS (sec)	PV (cP)	YP (lbs/ 100 ft^2)	Gels (lbs/ 100 ft^2)	600/ 300	HTHP (cc/30min)	NAP/ H_2O (ratio)	Cake (APT/ HT)	Solids (%)	pH	Alk	Cl- (mg/l)	$CaCl_2$	ES (v)	Loss (Bbls)
1	19-Jun	2,225'	10.40	76	19	12	8/14/17	50/31	6.8	79.1/20.9	2	14	-	3.2	38k	-	576	-
2	20-Jun	5,510'	10.60	66	22	11	8/15/18	55/33	4.2	78.6/21.4	2	13.9	-	3.0	35k	-	0	215
3	21-Jun	6,035'	10.70	69	23	12	9/17/19	58/35	4.2	78.6/21.4	2	13.9	-	2.8	35k	-	0	279
4	22-Jun	6,035'	10.55	90	22	10	8/16/20	58/35	5.7	70.9/29.1	2	13.9	-	2.5	56k	-	455	279
5	23-Jun	4,818'	10.45	83	52	33	8/14/19	52/33	5.7	72.1/27.9	2	13.9	-	2.7	55k	-	425	315
6	24-Jun	4,992'	10.80	90	21	17	13/15/19	59/38	5.7	68.6/31.4	2	11.3	-	2.7	45k	-	414	315
7	25-Jun	4,992'	10.80	84	18	16	8/12/17	52/34	5.6	74.1/25.9	2	12.5	-	2.8	41k	-	447	315
8	26-Jun	4,663'	10.40	65	17	11	8/11/15	45/28	5.4	76.7/23.3	2	11.3	-	2.9	44k	-	430	338
9	27-Jun	5,271'	10.80	73	17	12	7/11/14	46/29	5.1	75.9/24.1	2	14.6	-	2.9	40k	-	470	338
10	28-Jun	5,967'	10.70	59	17	13	8/11/15	47/30	5.0	77.1/22.9	2	14.9	-	3.0	34k	-	0	338
11	29-Jun	6,207'	10.65	61	20	12	10/13/15	52/32	5.0	78.8/21.2	2	13.2	-	2.9	30k	-	0	36
12	30-Jun	6,207'	10.65	61	20	12	10/13/15	52/32	5.0	78.8/21.2	2	13.2	-	2.9	30k	-	0	36

WELL LOCATION PLAT

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



VICINITY MAP



STAKED ON 3/16/12
VERTICAL CONTROL DATUM WAS BASED UPON CONTROL POINT 50 WITH AN ELEVATION OF 2164.3'

THIS SURVEY AND PLAT IS BEING PROVIDED AT THE REQUEST OF FABIAN KJORSTAD OF OASIS PETROLEUM. I CERTIFY THAT THIS PLAT CORRECTLY REPRESENTS WORK PERFORMED BY ME OR UNDER MY SUPERVISION AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

DARYL D. KASEMAN LS–3880

REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS–3880
DATE: 4/5/12
NORTH DAKOTA

1/7 SHEET NO.	INTERSTATE ENGINEERING — Professionals you need, people you trust	Interstate Engineering, Inc. P.O. Box 648, 425 East Main Street, Sidney, Montana 59270, Ph (406) 433-5617, Fax (406) 433-5618, www.iengi.com, Other offices in Minnesota, North Dakota and South Dakota	OASIS PETROLEUM NORTH AMERICA, LLC WELL LOCATION PLAT SECTION 31, T153N, R100W MCKENZIE COUNTY, NORTH DAKOTA; Drawn By: B.H.H.; Project No.: S12-09-068; Checked By: D.D.K.; Date: APRIL 2012	Revision No. / Date / By / Description


Vertical Section View
Surface Location:
1125' FWL & 1710' FSL
NW SW Sec. 31, T153N, R100W
McKenzie County, ND
Bottom Hole Location
1,096.59' N & 297.73' E
of surface location or approx.
2,806.59' FNL & 1,422.73' FWL
SE SW Sec. 31 T153N, R100E
31
N-S
W-E

4/7
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
QUAD LOCATION MAP
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description

COUNTY ROAD MAP

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



SCALE: 1" = 2 MILE

SHEET NO.				Revision No.	Date	By	Description
5/7	INTERSTATE ENGINEERING — Professionals you need, people you trust	Interstate Engineering, Inc. P.O. Box 648 425 East Main Street Sidney, Montana 59270 Ph (406) 433-5617 Fax (406) 433-5618 www.iengi.com Other offices in Minnesota, North Dakota and South Dakota	OASIS PETROLEUM NORTH AMERICA, LLC COUNTY ROAD MAP SECTION 31, T153N, R100W MCKENZIE COUNTY, NORTH DAKOTA Drawn By: B.H.H. Project No.: S12-09-068 Checked By: D.D.K. Date: APRIL 2012				

PAD LAYOUT

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 4/5/12 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

NOTE: All utilities shown are preliminary only, a complete utilities location is recommended before construction.

Revision No.	Date	By	Description

OASIS PETROLEUM NORTH AMERICA, LLC
PAD LAYOUT
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By: B.H.H. Project No.: S12-09-068
Checked By: D.D.K. Date: APRIL 2012

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

INTERSTATE ENGINEERING
Professionals you need, people you trust

SHEET NO. 2/7

ACCESS APPROACH

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 4/5/12 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

NOTE: All utilities shown are preliminary only, a complete utilities location is recommended before construction.

3/7
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
ACCESS APPROACH
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description

DRILLING PLAN

PROSPECT/FIELD	0 — **Vertical Dakota Water Disposal Well**	**COUNTY/STATE**	McKenzie Co., ND
OPERATOR	Oasis Petroleum	**RIG**	TBD
WELL NAME	Buck Shot SWD 5300 31-31		
LOCATION	NWSW 31-153N-100W	Surface Location (survey plat): 1710' fsl	1125' fwl
EST. T.D.	5,965	**GROUND ELEV:**	2157 Finished Pad Elev. **Sub Hieght:** 15
		KB ELEV:	2172

PROGNOSIS: Based on 2,172' KB(est)

MARKER	**DEPTH (Surf Loc)**	**DATUM (Surf Loc)**
Pierre	2,022	150
Greenhorn	4,629	(2,457)
Mowry	5,044	(2,872)
Dakota Top	5,462	(3,290)
First Dakota Sand Top	5,516	(3,344)
First Dakota Sand Base	5,549	(3,377)
Second Dakota Sand Top	5,670	(3,498)
Second Dakota Sand Base	5,757	(3,585)
Third Dakota Sand Top	5,795	(3,623)
Third Dakota Sand Base	5,815	(3,643)
Forth Dakota Sand Top	5,837	(3,665)
Forth Dakota Sand Base	5,915	(3,743)

LOGS:

	Type	**Interval**
OH Logs:	Triple Combo up to casing, GR/Res to BSC; GR to surf	
CBL/GR:	Above top of cement/GR to base of casing	

DEVIATION: None

DST'S: None planned

CORES: None planned

MUDLOGGING: None planned

BOP: 3k blind, pipe & annular

Max. Anticipated BHP: 2947

Surface Formation: *Glacial till*

MUD:	**Interval**		**Type**	**WT**	**Vis**	**WL**	**Remarks**
Surface	0' -	2,125'	FW/Gel Lime Sweeps	8.6 - 8.9	28-34	NC	Circ Mud Tanks
Straight Hole	2,125' -	#REF!	Invert	8.8-9.5	40-60	HTHP	Circ Mud Tanks

CASING:	**Size**	**Wt ppf**	**Hole**	**Depth**	**Cement**	**WOC**	**Remarks**
Surface:	9 5/8"	36	13 1/2"	2,125	To surface	12 hours	
Intermediate:	7"	26	8 3/4"	5,965	2,125	12 hours	

PROBABLE PLUGS, IF REQ'D:

OTHER:	**MD**	**TVD**	**FNL/FSL**	**FEL/FWL**	**S-T-R**	**AZI**
Surface:	2,125	2,125	298' FNL	291' FWL	**T152N-R101W-Sec. 3**	N/A
Csg Pt/TD:	5,965	5,965	298' FNL	291' FWL	**T152N-R101W-Sec. 3**	N/A

Comments:

MWD survey every 100'
Drill to TD and log

Reserve pit fluids will be hauled to the nearest disposal site/Reserve pit solids will be solidified and reclaimed in the lined reserve pit

OASIS PETROLEUM

Geology: **ANELSON 06-12-2012** **Engineering:** **M Brown 6/13/2012**

Well Name:	Buck Shot SWD 5300 31-31H					
Location:	NW SW SEC. 31, T153N, R100W					
	1,710' FSL & 1,125' FWL					
Elevation:	2,157	Sub: 25'		KB:	2,182'	
Formation/ Zone	**Prog. Top**	**Prog. MSL Datum**	**Est. MD Top (ROP)**	**Est. TVD Top (E-Log)**	**Est. MLS Datum**	**Thickness**
Pierre	2,070'	112'			2,182'	4,644'
Greenhorne	4,639'	-2,457'	4,644'	4,644'	-2,462'	413'
Mowry	5,054'	-2,872'	5,060'	5,057'	-2,875'	414'
Dakota Top	5,472'	-3,290'	5,518'	5,471'	-3,289'	51'
First Dakota Sand Top	5,526'	-3,344'	5,588'	5,522	-3,340'	31'
First Dakota Sand Base	5,559'	-3,377'	5,631'	5,553'	-3,371'	113'
Second Dakota Sand Top	5,680'	-3,498'	5,864'	5,666'	-3,484'	97'
Second Dakota Sand Base	5,767'	-3,585'	6,154'	5,763'	-3,573'	37'
Third Dakota Sand Top	5,805'	-3,623'	6,264'	5,800'	-3,617'	16'
Third Dakota Sand Base	5,825'	-3,643'	6,301'	5,816'	-3,630'	38'
Forth Dakota Sand Top	5,847'	-3,665'	6,480'	5,854'	-3,678'	-

Compar	Oasis Petroleun	Job Number: 6370	Calculation Methoc Minimum Curvature
Field:	Baker	Magnetic Decl.: 8.46	Proposed Azimuth 14.2
Cty/Blk/	Mckenzie Co. ND	Grid Corr.: True North	Depth Reference Driller
Well Na	Buck Shot SWD 5300 31-31	Total Survey Corr.:	Tie Into:
Rig:	Precision Drilling 565	Target Info:	

No.	Tool Type	Survey Depth (ft)	Incl (°)	Azimuth (°)	Temp (F)	Course Lgth (ft)	TVD (ft)	VS (ft)	Coordinates +N/-S (ft)		+E/-W (ft)		Closure Dist (ft)	Ang (°)	DLS (°/100')	Bld Rate (°/100')	Wlk Rate (°/100')
Tie in Survey																	
0	Tie In	2225	0	0	0	0	2225	0	0		0		0	0	0	0	0
1	MWD	2254	0.5	132.9	80	29	2254	-0.06	0.09	S	0.09	E	0.13	132.9	1.72	1.7	458.3
2	MWD	2344	0.5	162.5	86	90	2344	-0.58	0.73	S	0.5	E	0.88	145.6	0.28	0	32.9
3	MWD	2433	0.5	180.8	87	89	2432.99	-1.29	1.49	S	0.61	E	1.61	157.7	0.18	0	20.6
4	MWD	2523	0.6	184.1	89	90	2522.99	-2.14	2.35	S	0.57	E	2.42	166.35	0.12	0.1	3.7
5	MWD	2612	0.6	173.8	91	89	2611.98	-3.03	3.28	S	0.59	E	3.33	169.83	0.12	0	-11.6
6	MWD	2702	0.6	173.1	93	90	2701.98	-3.91	4.21	S	0.7	E	4.27	170.63	0.01	0	-0.8
7	MWD	2792	0.5	179.1	96	90	2791.97	-4.73	5.07	S	0.76	E	5.13	171.5	0.13	-0.1	6.7
8	MWD	2881	0.6	198.2	98	89	2880.97	-5.57	5.91	S	0.62	E	5.94	174.02	0.23	0.1	21.5
9	MWD	2971	0.8	199	100	90	2970.96	-6.67	6.95	S	0.27	E	6.95	177.8	0.22	0.2	0.9
10	MWD	3060	0.9	204.4	102	89	3059.95	-7.98	8.17	S	0.22	W	8.17	181.57	0.14	0.1	6.1
11	MWD	3150	1	217.7	104	90	3149.94	-9.39	9.44	S	1	W	9.49	186.03	0.27	0.1	14.8
12	MWD	3240	1	208.5	105	90	3239.93	-10.87	10.75	S	1.85	W	10.91	189.77	0.18	0	-10.2
13	MWD	3329	0.9	208.2	107	89	3328.92	-12.3	12.05	S	2.55	W	12.31	191.96	0.11	-0.1	-0.3
14	MWD	3419	0.8	208.9	111	90	3418.91	-13.6	13.22	S	3.19	W	13.6	193.57	0.11	-0.1	0.8
15	MWD	3508	0.7	202.3	113	89	3507.9	-14.74	14.27	S	3.7	W	14.74	194.53	0.15	-0.1	-7.4
16	MWD	3598	0.7	203.1	114	90	3597.89	-15.82	15.28	S	4.12	W	15.83	195.09	0.01	0	0.9
17	MWD	3688	0.6	206.6	114	90	3687.89	-16.83	16.21	S	4.55	W	16.83	195.67	0.12	-0.1	3.9
18	MWD	3777	0.6	207.3	116	89	3776.88	-17.74	17.04	S	4.97	W	17.75	196.26	0.01	0	0.8
19	MWD	3867	0.6	214.6	118	90	3866.88	-18.64	17.84	S	5.45	W	18.66	196.99	0.08	0	8.1
20	MWD	3957	0.6	217.9	118	90	3956.87	-19.51	18.6	S	6.01	W	19.55	197.9	0.04	0	3.7
21	MWD	4046	0.6	215.7	120	89	4045.87	-20.37	19.35	S	6.57	W	20.44	198.75	0.03	0	-2.5
22	MWD	4136	0.5	219.1	118	90	4135.86	-21.17	20.04	S	7.09	W	21.26	199.49	0.12	-0.1	3.8
23	MWD	4225	0.4	219.4	120	89	4224.86	-21.8	20.58	S	7.53	W	21.92	200.11	0.11	-0.1	0.3
24	MWD	4315	0.3	216.4	122	90	4314.86	-22.3	21.01	S	7.87	W	22.44	200.54	0.11	-0.1	-3.3
25	MWD	4405	0.2	213.3	123	90	4404.86	-22.67	21.33	S	8.1	W	22.82	200.79	0.11	-0.1	-3.4
26	MWD	4494	0.1	212.6	123	89	4493.86	-22.89	21.53	S	8.23	W	23.05	200.91	0.11	-0.1	-0.8
27	MWD	4584	0.2	231.5	123	90	4583.86	-23.09	21.69	S	8.39	W	23.26	201.15	0.12	0.1	21
28	MWD	4673	0.3	275.4	125	89	4672.85	-23.25	21.77	S	8.74	W	23.46	201.89	0.23	0.1	49.3
29	MWD	4763	0.3	293.4	127	90	4762.85	-23.25	21.65	S	9.2	W	23.52	203.01	0.1	0	20
30	MWD	4852	0.6	299.1	127	89	4851.85	-23.09	21.33	S	9.82	W	23.48	204.71	0.34	0.3	6.4
31	MWD	4942	0.9	287.4	129	90	4941.84	-22.93	20.89	S	10.9	W	23.57	207.56	0.37	0.3	-13
32	MWD	5032	1.7	267.7	129	90	5031.82	-23.27	20.73	S	12.91	W	24.43	211.91	1.01	0.9	-21.9
33	MWD	5121	0.7	245.8	127	89	5120.8	-23.98	21.01	S	14.73	W	25.66	215.03	1.22	-1.1	-24.6
34	MWD	5211	0.4	218.3	129	90	5210.8	-24.61	21.48	S	15.42	W	26.44	215.68	0.43	-0.3	-30.6
35	MWD	5301	0.5	165.1	129	90	5300.79	-25.24	22.11	S	15.52	W	27.01	215.06	0.46	0.1	-59.1

36	MWD	5390	0.6	105.2	127	89	5389.79	-25.59	22.6	S	14.97	W	27.11	213.51	0.62	0.1	-67.3
37	MWD	5480	0.7	92.2	123	90	5479.78	-25.48	22.75	S	13.96	W	26.69	211.54	0.2	0.1	-14.4
38	MWD	5569	0.8	88.4	123	89	5568.78	-25.2	22.75	S	12.8	W	26.11	209.36	0.13	0.1	-4.3
39	MWD	5659	0.7	78.3	122	90	5658.77	-24.79	22.62	S	11.63	W	25.44	207.21	0.18	-0.1	-11.2
40	MWD	5748	1	78.7	122	89	5747.76	-24.21	22.36	S	10.34	W	24.64	204.81	0.34	0.3	0.4
41	MWD	5838	0.8	83.4	123	90	5837.75	-23.65	22.14	S	8.94	W	23.87	202	0.24	-0.2	5.2
42	MWD	5927	0.8	76	123	89	5926.74	-23.14	21.91	S	7.72	W	23.23	199.42	0.12	0	-8.3
43	PTB	6035	0.8	76	123	108	6034.73	-22.43	21.55	S	6.26	W	22.44	196.2	0	0	0

RPM Geologic

Operator:	Oasis Petrolwum
Well :	Buck Shot SWD 5300 31-31
MWD Providers	Ryan
Directional Supervision:	RPM

Section:	31	QQ:	NW SW	County:	Sheridan	State:	MT
Township:	153	N/S:	N	Footages:	1710	FN/SL:	S
Range:	100	E/W:	W		1125	FE/WL:	W

Vertical Section Plane: 14.2

#	MD	Inc.	Azm.	T.V.D.	Ver. Sect.	Coordinates +N / -S	+E / -W	DLS
Tie	**4405.00**	**0.20**	**213.30**	**4404.86**	**-22.67**	**-21.33**	**-8.10**	**0.11**
1	4493.00	0.30	184.30	4492.86	-23.04	-21.69	-8.20	0.18
2	4582.00	0.90	344.00	4581.85	-22.66	-21.25	-8.41	1.33
3	4672.00	5.10	19.80	4671.71	-18.07	-16.80	-7.25	4.89
4	4762.00	4.90	18.20	4761.37	-10.25	-9.39	-4.69	0.27
5	4851.00	4.80	15.90	4850.05	-2.74	-2.20	-2.49	0.25
6	4941.00	4.40	12.50	4939.76	4.48	4.80	-0.71	0.54
7	4986.00	5.80	27.30	4984.59	8.42	8.50	0.71	4.24
8	5030.00	11.90	23.60	5028.04	15.06	14.64	3.55	13.92
9	5075.00	16.60	26.40	5071.65	25.93	24.66	8.27	10.55
10	5120.00	16.50	27.10	5114.78	38.44	36.10	14.03	0.50
11	5165.00	15.90	27.80	5157.99	50.66	47.24	19.82	1.40
12	5210.00	15.90	27.70	5201.27	62.65	58.15	25.56	0.06
13	5254.00	20.40	24.30	5243.07	76.06	70.49	31.52	10.50
14	5299.00	23.50	19.70	5284.81	92.72	86.09	37.78	7.87
15	5344.00	27.40	13.80	5325.44	112.02	104.60	43.27	10.33
16	5389.00	29.30	13.00	5365.04	133.38	125.38	48.22	4.31
17	5433.00	32.00	13.10	5402.89	155.81	147.23	53.28	6.14
18	5478.00	36.90	12.40	5439.99	181.25	172.06	58.89	10.92
19	5523.00	41.50	11.20	5474.85	209.65	199.89	64.69	10.36
20	5568.00	42.70	11.40	5508.24	239.78	229.47	70.60	2.68
21	5613.00	46.50	12.20	5540.28	271.35	260.40	77.07	8.54
22	5657.00	50.90	12.60	5569.31	304.38	292.67	84.17	10.02
23	5702.00	57.90	12.10	5595.49	340.92	328.39	91.99	15.58
24	5747.00	62.10	12.50	5617.98	379.87	366.46	100.29	9.36
25	5792.00	63.10	13.10	5638.69	419.80	405.42	109.14	2.52
26	5837.00	68.40	12.80	5657.17	460.81	445.39	118.33	11.79
27	5926.00	71.70	14.80	5687.53	544.45	526.62	138.30	4.27
28	5971.00	71.50	15.30	5701.74	587.14	567.85	149.38	1.14
29	6016.00	69.80	15.10	5716.65	629.59	608.82	160.52	3.80
30	6061.00	69.90	14.90	5732.15	671.84	649.63	171.45	0.47
31	6106.00	70.40	15.10	5747.43	714.16	690.51	182.40	1.19
32	6150.00	70.60	15.30	5762.12	755.63	730.54	193.28	0.62
33	6241.00	70.70	14.90	5792.27	841.48	813.43	215.65	0.43
34	6337.00	69.60	16.10	5824.87	931.75	900.44	239.77	1.64
35	6432.00	69.80	16.40	5857.83	1020.79	985.98	264.70	0.36
36	6496.00	69.80	16.70	5879.93	1080.80	1043.56	281.81	0.44
Project	6555.00	69.80	16.70	5900.30	1136.12	1096.59	297.73	0.00

Oasis Petroleum North America LLC. Buck Shot SWD 5300 31-31H
Lithology Report

Logging of the Buck Shot SWD 5300 31-31H well by RPM Geologic geologists Tyson Zentz and Adam Graves commenced on June 18th, 2013. Rig crews began catching samples at 30' intervals at a depth of 4,000' in the Pierre formation through the forth sand bench of the Dakota formation. Samples were examined using a digital stereoscope. HCL was used to aid in determining lithology. Quantifiers in the descriptions are as follows in order of increasing magnitude; trace, rare, occasional, common and abundant.

Initiated Logging of Pierre formation 4,000' TVD

4000-4030 SHALE: light to medium gray, occasional orange, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4030-4060 SHALE: light to medium gray, occasional orange, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4060-4090 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4090-4120 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4120-4150 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4150-4180 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4180-4210 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4210-4240 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4240-4270 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4270-4300 SHALE: light to medium gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4300-4330 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4330-4360 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4360-4390 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4390-4420 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

4420-4450 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, slightly calcareous, earthy texture, no visible porosity

4450-4480 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4480-4510 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4510-4540 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4540-4570 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4570-4600 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4600-4644 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, calcareous, earthy texture, no visible porosity

Greenhorn Formation 4,644' TVD (-2,462')

4644-4660 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4660-4690 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4690-4720 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4720-4750 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4750-4780 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4780-4810 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4810-4840 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4840-4870 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, micaceous, calcareous, earthy texture, no visible porosity

4870-4900 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, slightly calcareous, earthy texture, no visible porosity

4900-4930 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, slightly calcareous, earthy texture, no visible porosity

4930-4960 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, slightly calcareous, earthy texture, clay in part, no visible porosity

4960-4990 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, slightly calcareous, earthy texture, clay in part, no visible porosity

4990-5020 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, slightly calcareous, earthy texture, clay in part, no visible porosity

5020-5052 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, slightly calcareous, earthy texture, clay in part, no visible porosity

Mowry Formation 5,052' TVD (-2,870')

5052-5080 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5080-5110 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5110-5140 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5140-5170 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5170-5200 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5200-5230 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5230-5260 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5260-5290 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5290-5320 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5320-5350 SHALE: medium to dark grained, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5350-5380 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5380-5410 SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5410-5440 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5440-5471 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

Dakota Top 5,471' TVD (-3,289')

5471-5500 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5500-5522 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

First Dakota Sand Top 5,522’ TVD (-3,340’)

5522-5555 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

First Dakota Sand Base 5,555’ TVD (-3,373’)

5555-5590 SILTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5590-5620 SILTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5620-5665 SILTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

Second Dakota Sand Top 5,665’ TVD (-3,483’)

5665-5680 SILTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5680-5710 SILTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5710-5740 SILTY SANDSTONE: light gray, light brown to brown, firm to friable, very fine grained to fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5740-5759 SILTY SANDSTONE: light brown to brown, firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

Second Dakota Sand Base 5,759’ TVD (-3,577’)

5759-5804 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

Third Dakota Sand Top 5,804’ TVD (-3,622’)

5804-5821 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

Third Dakota Sand Base ***5,821' TVD (-3,639')***

5821-5853 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

Forth Dakota Sand Top ***5,853' TVD (-3,670')***

5853-5890 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5890-5920 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5920-5950 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5950-5980 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5980-6010 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

6010-6035 SILTY SANDSTONE: light gray to gray, trace brown firm to friable, fine grained, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

Total Depth Reached: 6,035' MD June 20th 2013 at 3:20 pm Central Time

S-Well Initiated Logging of Pierre formation 4,440’ MD

4440-4470 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4470-4500 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4500-4530 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4530-4560 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4560-4590 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4590-4620 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4620-4644 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

Greenhorn Formation 4,644’ MD, 4,644’ TVD (-2,462’)

4644-4680 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4680-4710 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4710-4740 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4740-4770 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4770-4800 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4800-4830 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4830-4860 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4860-4890 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4890-4920 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4920-4950 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4950-4980 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

4980-5010 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

5010-5040 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

5040-5060 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

Mowry Formation 5,060’ MD, 5,057’ TVD (-2,875’)

5060-5100 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

5100-5130 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

5130-5160 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

5160-5190 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

5190-5220 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5220-5250 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5250-5280 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5280-5310 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5310-5340 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5340-5370 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5370-5400 SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5400-5430 SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5430-5460 SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5460-5490 SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity

5490-5518 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

Dakota Top 5,518’ MD, 5,471’ TVD (-3,289’)

5520-5550 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5550-5588 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, calcareous cemented, quartz in part, possible intergranular porosity; SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

First Dakota Sand Top 5,588’ MD, 5,522’ TVD (-3,340’)

5588-5610 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5610-5631 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine to fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

First Dakota Sand Base 5,631' MD, 5,553' TVD (-3,371')

5631-5670 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine to fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5670-5700 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine to fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5700-5730 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine to fine grain, calcareous cemented, quartz in part, possible intergranular porosity; SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5730-5760 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine to fine grain, calcareous cemented, quartz in part, possible intergranular porosity; SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5760-5790 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5790-5820 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5820-5864 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

Second Dakota Sand Top 5,864' MD, 5,666' TVD (-3,484')

5864-5880 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5880-5910 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5910-5940 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5940-5970 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

5970-6000 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

6000-6030 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

6030-6060 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

6060-6090 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

6090-6120 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

6120-6154 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

Second Dakota Sand Base ***6,154’ MD, 5,763’ TVD (-3,573’)***

6154-6180 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, very fine grain, calcareous cemented, quartz in part, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, clay in part, no visible porosity

6180-6210 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6210-6240 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6240-6264 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

Third Dakota Sand Top ***6,264’ MD, 5,800’ TVD (-3,617’)***

6264-6301 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

Third Dakota Sand Base ***6,301’ MD, 5,816’ TVD (-3,630’)***

6301-6330 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6330-6360 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6360-6390 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6390-6420 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6420-6450 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6450-6480 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

Forth Dakota Sand Top ***6,480’ MD, 5,854’ TVD (-3,678’)***

6480-6510 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6510-6540 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

6540-6555 SILTY SANDSTONE: light gray, white, trace light brown, firm to friable, sub rounded to sub angular, fine to very fine grain, calcareous cemented, possible intergranular porosity; trace SHALE: medium to dark gray, trace light gray, soft to friable, sub blocky to blocky, earthy texture, no visible porosity

Total Depth Reached: 6,555' MD July 1st 2013 at 10:45 am Central Time

RPM Geologic

SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

Well File No.
90244

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- [x] Notice of Intent — Approximate Start Date: **June 17, 2013**
- [ ] Report of Work Done — Date Work Completed:
- [ ] Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

- [ ] Drilling Prognosis
- [ ] Redrilling or Repair
- [x] Casing or Liner
- [ ] Plug Well
- [ ] Supplemental History
- [ ] Temporarily Abandon
- [ ] Other
- [ ] Spill Report
- [ ] Shooting
- [ ] Acidizing
- [ ] Fracture Treatment
- [ ] Change Production Method
- [ ] Reclamation

Well Name and Number					
Buck Shot SWD 5300 31-31					
Footages		Qtr-Qtr	Section	Township	Range
1717 F S L	1153 F W L	NWSW	21	153 N	100 W
Field	Pool	County			
Baker	Dakota Group	McKenzie			

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s)			
Address	City	State	Zip Code

DETAILS OF WORK

Oasis Petroleum respectfully requests to make the following changes to the Buck Shot SWD 5300 31-31 completion plan:

TD 8-3/4" OH at a depth of approximately 5,775' TVD and run 7" 26# L-80 casing to TD and cement with original planned cement top to surface shoe. Oasis Petroleum then intends to drill out of 7" casing with 6" OH. Wellbore will not penetrate the Swift formation (estimated TVD top of 5,915' TVD) Completion to be left open hole.

Oasis Petroleum still intends to perforate and inject through 7" casing within Dakota group upon completion. No other changes to permitted slant plan. Tubing packer will remain below the base of the Mowry.

* Note that packer must be below base of Mowry
* Contact Stephen Fried or Richard Dunn if swift is penetrated

Company			Telephone Number
Oasis Petroleum North America LLC			(281) 404-9634
Address			
1001 Fannin, Suite 1500			
City		State	Zip Code
Houston		TX	77002
Signature	Printed Name		
Mike Brown	Mike Brown		
Title	Date		
Drilling Engineer II	June 27, 2013		
Email Address			
mbrown@oasispetroleum.com			

FOR STATE USE ONLY

[ ] Received	[x] Approved w/ amendment
Date	6-27-2013
By	[signature]
Title	UNDERGROUND INJECTION SUPERVISOR

Buck Shot SWD 5300 31-31H
WELLBORE SCHEMATIC

API #: 33-053-90244
FORMATION: Dakota
FIELD: Camp



OASIS PETROLEUM INC.

Buck Shot SWD 5300 31-31 T153N-R100W Sec. 31 1717' FSL & 1153' FWL	Status: Planned McKenzie County, North Dakota Updated: 6/27/2013

APPLICATION FOR INJECTION - FORM 14

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 18669 (02-2011)

FEB 2013
RECEIVED
ND OIL & GAS
DIVISION

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM. PLEASE SUBMIT THE ORIGINAL AND TWO COPIES.
APPROVAL MUST BE OBTAINED BEFORE WORK COMMENCES.

Permit Type: ☐ Enhanced Recovery ☑ Saltwater Disposal ☐ Gas Storage	Injection Well Type: ☐ Converted ☑ Newly Drilled		Commercial SWD: ☐ Yes ☑ No
Operator: **Oasis Petroleum North America LLC**	Telephone Number: **(281) 404-9500**	Will Oil be Skimmed? ☑ Yes ☐ No	
Address: **1001 Fannin, Suite 1500**	City: **Houston**	State: **TX**	Zip Code: **77002**
Well Name and Number: **Buck Shot SWD 5300 31-31H**	Field or Unit: **Camp**		

LOCATIONS

At Surface: **~~1710~~ 1717** F S L	**~~1125~~ 1153** F W L	Qtr-Qtr: **NWSW**	Section: **31**	Township: **153** N	Range: **100** W	County: **McKenzie**
Bottom Hole Location: **1982** F N L	**1546** F W L	Qtr-Qtr: **NWSW**	Section: **31**	Township: **153** N	Range: **100** W	County: **McKenzie**

Geologic Name of Injection Zone: **Dakota Group**	Top: **5472** Feet	Injection Interval: **5498'-5794' TVD** Feet	
Geologic Name of Top Confining Zone: **Skull Creek**	Thickness: **250** Feet	Geologic Name of Bottom Confining Zone: **Swift**	Thickness: **460** Feet
Bottom Hole Fracture Pressure of the Top Confining Zone: **4369** PSI		Gradient: **0.80** PSI/Ft	
Estimated Average Injection Rate and Pressure: **3000** BPD @ **1000** PSI		Estimated Maximum Injection Rate and Pressure: **5000** BPD @ **1500** PSI	
Geologic Name of Lowest Known Fresh Water Zone: **Fox Hills**			Depth to Base of Fresh Water Zone: **2022** Feet
Total Depth of Well (MD & TVD): **6936 MD / 5788 TVD** Feet	Logs Previously Run on Well: **Triple combo through Mowry, GR/Res to BSC, GR to surface to be run after TD**		

CASING, TUBING, AND PACKER DATA (Check If Existing)

NAME OF STRING	SIZE	WEIGHT (Lbs/Ft)	SETTING DEPTH	SACKS OF CEMENT	TOP OF CEMENT	TOP DETERMINED BY
Surface ☑	9 5/8"	36	2170	760	Surface	Visual Observation
Intermediate ☐						
Long String ☑	7"	26	~~6938~~	~~595~~ 496	2170	CBL

				TOP	BOTTOM	SACKS OF CEMENT
Liner ☐						

				TYPE
Proposed Tubing				

Proposed Packer Setting Depth: **5600** (5478) Feet	Model: **Internally coated Baker lockset**	☑ Compression ☐ Permanent ☐ Tension

Modified to Directional

FOR STATE USE ONLY

Permit Number and Well File Number: 90244	
UIC Number: W0346S0820D	Approval Date: 6-27-2013
By: [signature]	
Title: UNDERGROUND INJECTION SUPERVISOR	

COMMENTS

I hereby swear or affirm that the information provided is true, complete and correct as determined from all available records.		Date **January 15, 2013**
Signature	Printed Name **Tommy Thompson**	Title **Sr Facilities Engineer**

Above Signature Witnessed By

Witness Signature	Witness Printed Name **Brandi Terry**	Witness Title **Regulatory Specialist**

Instructions

1. Attach a list identifying all attachments.
2. The operator, well name and number, field or unit, well location, and any other pertinent data shall coincide with the official records on file with the Commission. If it does not, an explanation shall be given.
3. If an injection well is to be drilled, an Application for Permit to Drill - Form 1 (SFN 4615) shall also be completed and accompanied by a plat prepared by a registered surveyor and a drilling fee.
4. Attach a lithologic description of the proposed injection zone and the top and bottom confining zones.
5. Attach a plat depicting the area of review (1/4-mile radius) and detailing the location, well name, and operator of all wells in the area of review. Include: injection wells, producing wells, plugged wells, abandoned wells, drilling wells, dry holes, and water wells. The plat shall also depict faults, if known or suspected.
6. Attach a description of the needed corrective action on wells penetrating the injection zone in the area of review.
7. Attach a brief description of the proposed injection program.
8. Attach a quantitative analysis from a state-certified laboratory of fresh water from the two nearest fresh water wells. Include legal descriptions.
9. Attach a quantitative analysis from a state-certified laboratory of a representative sample of water to be injected.
10. Attach a list identifying all source wells, including location.
11. Attach a legal description of land ownership within the area of review. List ownership by tract or submit in plat form.
12. Attach an affidavit of mailing certifying that all landowners within the area of review have been notified of the proposed injection well. This notice shall inform the landowners that comments or objections may be submitted to the Commission within 30 days, or that a hearing will be held at which comments or objections may be submitted, whichever is applicable. Include copies of letters sent.
13. Attach all available logging and test data on the well which has not been previously submitted.
14. Attach schematic drawings of the injection system including current well bore construction and proposed well bore and surface facility construction.
15. Attach a Sundry Notice - Form 4 (SFN 5749) detailing the proposed procedure.
16. Read Section 43-02-05-04 of the North Dakota Administrative Code to ensure that this application is complete.
17. The original and two copies of this application and attachments shall be filed with the Industrial Commission of North Dakota, Oil and Gas Division, 600 East Boulevard, Dept. 405, Bismarck, ND 58505-0840.



BUCK SHOT SWD 5300 31-31
153N - 100W Section 31
McKenzie County, North Dakota

OASIS PETROLEUM

Exhibit 3 – Proposed Injection Program

January 14, 2013

Buck Shot SWD 5300 31-31
Oasis Petroleum North America, LLC
Section 31, T153N R100W
McKenzie County, North Dakota

Application for Fluid Injection

PROPOSED INJECTION PROGRAM

The Buck Shot SWD 5300 31-31 well will be used to inject produced water from wells in the Indian Hills area - Oasis Bakken and Three Forks wells already on production, in the process of completion, and those soon to be drilled in the four township area of 152-153N and 100-101W into the Dakota formation. Injection depths will be determined after the well is drilled and logged.

The Buck Shot SWD will utilize the existing tanks and pump facilities of the Oasis-operated BWL SWD 5201 11-3. The injection pump will send water to both the BWL SWD and Buck Shot SWD. There will be a pressure transducer at the outlet of the pump that limits the maximum pressure of the discharge to the permitted pressure. This pressure transducer will communicate to the VFD that controls the pump to maximize the efficiency of the pump as well as shut it off at the max allowable pressure. There will be 2 flow meters after the tee in the discharge line, one for the BWL SWD and the other for the Buck Shot SWD.

The flowline to the Buck Shot wellhead will tap into the existing 6 inch flexsteel pipe that is currently in operation for the BWL SWD. This flowline is rated for 2250 psi, approximately 700 psi above the maximum allowable pressure for the Buck Shot SWD. The lease operator will be on location on a daily basis to monitor both SWD locations and the flowline that feeds both the BWL SWD and Buck Shot SWD.

The wellhead and horizontal lateral of the Oasis-operated Lewis Federal 5300 31-31H well is within the ¼ mile area of review but no corrective action is required as the lateral of the Lewis Federal 5300 31-31H is completed within the Bakken Formation which is separated from the Dakota Group by the Swift confining layer and several thousand feet of other impermeable shales.

The horizontal lateral of the Oasis-operated Gramma Federal 5300 41-31T well is within the ¼ mile area of review but no corrective action is required as this lateral was drilled within the Bakken Formation which is separated from the Dakota Group by the Swift confining layer and several thousand feet of other impermeable shales. The vertical portion of the Gramma Federal 5300 41-31T lies outside of the ¼ mile AOR for the Buck Shot SWD.

The proposed Buck Shot SWD is needed to provide a more local disposal facility in the area to reduce costs and ease the burden on regional disposal wells, it will supplement the existing BWL SWD. The anticipated initial injection rate of the well will be 5,000 bwpd at 1,000 psig pressure. However, this rate may increase with additional drilling in the area, subject to the maximum pressure ceiling.

Fried, Stephen J.

From: Mike Brown <mbrown@oasispetroleum.com>
Sent: Thursday, June 27, 2013 5:01 PM
To: Fried, Stephen J.
Subject: Updated Buck Shot SWD numbers

Stephen,

Here is the requested information. These are based on current drilling data and the plan forward (as detailed in schematic). Please let me know if there is anything else that I can do to help you out.

Actual Surface shoe: 2,225' (Precision 565 - 25' KB)

7" Casing:
Displacement: 680' North, 170' East
Coordinates: 2397' FSL, 1323' FWL

7" Cement:
Lead Cement: 170sks (56bbl)
Tail Cement: 326 sks (72bbl)

Updated BHL (OH):
Displacement: 1,049' North, 262' East
Coordinates: 2,482' FNL, 1415' FWL

Thanks,

Mike Brown
Drilling Engineer II
Oasis Petroleum
1001 Fannin, Suite 1500
Houston, Texas 77002
281-404-9634 Office
281-732-7482 Cell
mbrown@oasispetroleum.com

Oasis Petroleum
Well Summary
Buck Shot SWD 5300 31-31H
Section 31 T153N R100W
McKenzie County, ND

SURFACE CASING AND CEMENT DESIGN

							Make-up Torque (ft-lbs)		
Size	Interval	Weight	Grade	Coupling	I.D.	Drift	Minimum	Optimum	Max
9-5/8"	0' to 2,170'	36	J-55	LTC	8.921"	8.765"	3400	4530	5660

Interval	Description	Collapse	Burst	Tension	Cost per ft
		(psi) a	(psi) b	(1000 lbs) c	
0' to 2,170'	9-5/8", 36#, J-55, LTC, 8rd	2020 / 1.99	3520 / 3.47	453 / 2.71	

API Rating & Safety Factor

a) Based on full casing evacuation with 9.0 ppg fluid on backside (2,170' setting depth).
b) Burst pressure based on 9 ppg fluid with no fluid on backside (2,170' setting depth).
c) Based on string weight in 9.0 ppg fluid at 2,170' TVD plus 100k# overpull. (Buoyed weight equals 67k lbs.)

Cement volumes are based on 9-5/8" casing set in 13-1/2" hole with 55% excess to circulate cement back to surface. Mix and pump the following slurry.

Pre-flush (Spacer): **20 bbls** fresh water

Lead Slurry: **460 sks** (238 bbls) Conventional system with 94 lb/sk cement, 4% extender, 2% expanding agent, 2% CaCl2 and 0.25 lb/sk lost circulation control agent

Tail Slurry: **300 sks** (61 bbls) Conventional system with 94 lb/sk cement, 3% NaCl, and 0.25 lb/sk lost circulation control agent

Oasis Petroleum
Well Summary
Buck Shot SWD 5300 31-31H
Section 31 T153N R100W
McKenzie County, ND

INTERMEDIATE CASING AND CEMENT DESIGN

Intermediate Casing Design

							Make-up Torque (ft-lbs)		
Size	**Interval**	**Weight**	**Grade**	**Coupling**	**I.D.**	**Drift**	**Minimum**	**Optimum**	**Max**
	6148								
7"	0' – ~~6,936'~~	26	L-80	LTC	6.276"	6.151"	3900	4900	5900

**Special Drift

Interval	Description	Collapse	Burst	Tension
		(psi) a	(psi) b	(1000 lbs) c
0' – 6,936'	7", 26#, L-80, LTC, 8rd	5410 / 1.80	7240 / 1.37	511 / 2.02

API Rating & Safety Factor

a) Collapse pressure based on full casing evacuation with 10 ppg fluid on backside (5,788' setting depth).
b) Burst pressure based on 5,000 psi max stimulation pressure plus 10.0 ppg fluid inside casing with 9.0 ppg fluid on backside (5,788' setting depth).
c) Based on string weight in 10 ppg fluid at 6,936' MD plus 100k# overpull. (Buoyed weight equals 126k lbs.)

Cement volumes are estimates based on 7" casing set in an 8-3/4" hole with 30% excess. TOC = 2,125'

Pre-flush (Spacer): **20 bbls CW8 System**
20 bbls fresh water

Lead Slurry: 170 ~~165 sks~~ (56 ~~76~~ bbls) 11.5 lb/gal LiteCRETE with 27.005 lb/sk Extender, 10% NaCl, 0.40% Dispersant, 0.25% Retarder, 0.20% Anti-foam, 0.10% Retarder, 0.25 lb/sk lost circulation control agent

Tail Slurry: 326 ~~430 sks~~ (72 ~~119~~ bbls) 15.6 lb/gal conventional system with 94 lb/sk cement, 10% NaCl, 35% Silica, 0.20% dispersant, 0.40% fluid loss agent, 0.10% retarder, and 0.25 lb/sk lost circulation control agent

SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

Well File No. **90244**

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- [x] Notice of Intent — Approximate Start Date: **February 1, 2013**
- [ ] Report of Work Done — Date Work Completed:
- [ ] Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

- [ ] Drilling Prognosis
- [ ] Redrilling or Repair
- [ ] Casing or Liner
- [ ] Plug Well
- [ ] Supplemental History
- [ ] Temporarily Abandon
- [x] Other **Amend approved APD**
- [ ] Spill Report
- [ ] Shooting
- [ ] Acidizing
- [ ] Fracture Treatment
- [ ] Change Production Method
- [ ] Reclamation

Well Name and Number					
Buck Shot SWD 5300 31-31H					
Footages		Qtr-Qtr	Section	Township	Range
1717 F S L	1153 F W L	NWNW	31	153 N	100 W
Field	Pool	County			
Baker	Dakota Group	McKenzie			

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s)			
Address	City	State	Zip Code

DETAILS OF WORK

Oasis Petroleum North America LLC respectfully requests its approved APD to drill the Buck Shot SWD 5300 31-31 be revised to allow for a horizontal completion.

No additional landowners be impacted by this change.
The horizontal lateral of the Oasis-operated Gramma Federal 5300 41-31T well is within the ¼ mile area of review but no corrective action is required as this lateral was drilled within the Bakken Formation which is separated from the Dakota Group by the Swift confining layer and several thousand feet of other impermeable shales. The vertical portion of the Gramma Federal 5300 41-31T lies outside of the ¼ mile AOR for the Buck Shot SWD.

Company		Telephone Number
Oasis Petroleum North America LLC		281-404-9491
Address		
1001 Fannin, Suite 1500		
City	State	Zip Code
Houston	TX	77002
Signature	Printed Name	
	Tommy Thompson	
Title	Date	
Sr. Facilities Engineer	December 6, 2012	
Email Address		
tthompson@oasispetroleum.com		

FOR STATE USE ONLY

[ ] Received	[x] Approved
Date	6-28-2013
By	
Title	UNDERGROUND INJECTION SUPERVISOR

WELL LOCATION PLAT

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31H"
1717 FEET FROM SOUTH LINE AND 1153 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



– MONUMENT – RECOVERED
– MONUMENT – NOT RECOVERED

VICINITY MAP



STAKED ON 12/20/12
VERTICAL CONTROL DATUM WAS BASED UPON CONTROL POINT 10 WITH AN ELEVATION OF 2220.7'

THIS SURVEY AND PLAT IS BEING PROVIDED AT THE REQUEST OF FABIAN KJORSTAD OF OASIS PETROLEUM. I CERTIFY THAT THIS PLAT CORRECTLY REPRESENTS WORK PERFORMED BY ME OR UNDER MY SUPERVISION AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

DARYL D. KASEMAN LS-3880

REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS-3880
DATE: 1/03/13
NORTH DAKOTA

1/8
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
WELL LOCATION PLAT
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD

SECTION BREAKDOWN

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31H"
1717 FEET FROM SOUTH LINE AND 1153 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



VICINITY MAP



THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 1/03/13 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

ALL AZIMUTHS ARE BASED ON G.P.S. OBSERVATIONS. THE ORIGINAL SURVEY OF THIS AREA FOR THE GENERAL LAND OFFICE (G.L.O.) WAS 1901. THE CORNERS FOUND ARE AS INDICATED AND ALL OTHERS ARE COMPUTED FROM THOSE CORNERS FOUND AND BASED ON G.L.O. DATA. THE MAPPING ANGLE FOR THIS AREA IS APPROXIMATELY −0°02'.

REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS−3880
DATE: 1/03/13
NORTH DAKOTA

2/8
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
SECTION BREAKDOWN
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By: B.H.H. | Project No.: S12-09-068
Checked By: D.D.K. | Date: APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD

DRILLING PLAN

PROSPECT/FIELD	[illegible] Vertical Dakota Water Disposal Well	**COUNTY/STATE**	[illegible]
OPERATOR	[illegible]	**RIG**	[illegible]
WELL NAME	[illegible]		
LOCATION	[illegible]	Surface Location (survey plat): [illegible]	[illegible]
EST. T.D.	4,966	**GROUND ELEV:** [illegible] Finished Pad Elev.	**Sub Hieght:** [illegible]
		KB ELEV: [illegible]	

PROGNOSIS: [illegible]

MARKER	DEPTH (Surf Loc)	DATUM (Surf Loc)
Pierre	2,070	112
Greenhorn	4,639	(2,457)
Mowry	5,054	(2,872)
Dakota Top	5,472	(3,290)
First Dakota Sand Top	5,526	(3,344)
First Dakota Sand Base	5,559	(3,377)
Second Dakota Sand Top	5,680	(3,498)
Second Dakota Sand Base	5,767	(3,585)
Third Dakota Sand Top	5,805	(3,623)
Third Dakota Sand Base	5,825	(3,643)
Forth Dakota Sand Top	5,847	(3,665)
Forth Dakota Sand Base/Swift	5,917	(3,743)

LOGS: Type / Interval

OH Logs: Triple Combo up to casing, GR/Res to BSC; GR to surf

CBL/GR: Above top of cement/GR to base of casing

DEVIATION: None

DST'S: None planned

CORES: None planned

MUDLOGGING: None planned

BOP: 11" 5000 psi blind, pipe & annular

Max. Anticipated BHP: [illegible]

Surface Formation: *Glacial till*

MUD:	Interval		Type	WT	Vis	WL	Remarks
Surface	0' -	2,170'	FW/Gel Lime Sweeps	8.6 - 8.9	28-34	NC	Circ Mud Tanks
Intermediate	2,170' -	5,752'	Invert	8.8-9.5	40-60	HTHP	Circ Mud Tanks
Slant	5,752' -	6,936'	Invert	9.0-10.0	40-60	HTHP	Circ Mud Tanks

CASING:	Size	Wt ppf	Hole	Depth	Cement	WOC	Remarks
Surface:	9 5/8"	36	13 1/2"	2,170	To surface	12 hours	
Intermediate:	7"	26	8 3/4"	5,752	~~2,126~~ 2170	12 hours	
Liner:	4.5"	11.60	6"	6,936	4,900	12 hours	

PROBABLE PLUGS, IF REQ'D:

OTHER:	MD	TVD	FNL/FSL	FEL/FWL	S-T-R	AZI
Surface:	2,170	2,170	1717' FSL	1153' FWL	T153N-R100W-Sec. 31	
KOP:	4,966	4,966	1717' FSL	1153' FWL	T153N-R100W-Sec. 31	
EOC:	5,736	5,524	2147' FSL	1262' FWL	T153N-R100W-Sec. 31	14.2
Casing Point:	5,752	5,528	2163' FSL	1266' FWL	T153N-R100W-Sec. 31	14.2
Dakota Slant TD	6,936	5,794	1982' FNL	1546' FWL	T153N-R100W-Sec. 31	14.2

Comments:

Drill Vert. and Pilot Hole to ~6,000'. Run SLB Log Suite

MWD survey every 100'. Place Cement Kickoff Plug

TIH with 8-3/4" Curve assembly and build curve. MWD Survey every 30'. Land Curve @77deg, just above interpreted sand package and run 7" 26# csg

Drill out with 6" bit and rotate down ~1200' to TD. MWD Survey every 30'. Run 4.5" Liner and cement

Reserve pit fluids will be hauled to the nearest disposal site/Reserve pit solids will be solidified and reclaimed in the lined reserve pit

OASIS PETROLEUM

Geology: [illegible] **Engineering: M. Brown 1/3/2012** 1/15/2013

PAD LAYOUT

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31H"
1717 FEET FROM SOUTH LINE AND 1153 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS-3880
DATE: 1/03/13
NORTH DAKOTA

THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 1/03/13 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

0 80
1" = 80'

NOTE: All utilities shown are preliminary only, a complete utilities location is recommended before construction.

3/8
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
PAD LAYOUT
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD

ACCESS APPROACH

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31H"
1717 FEET FROM SOUTH LINE AND 1153 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 1/03/13 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

R101W R100W

EX. 33' R/W

0 300

1" = 300'

NOTE: All utilities shown are preliminary only, a complete utilities location is recommended before construction.

4/8
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
ACCESS APPROACH
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By: B.H.H. Project No.: S12-09-068
Checked By: D.D.K. Date: APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD



5/8
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
QUAD LOCATION MAP
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD

COUNTY ROAD MAP

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31H"
1717 FEET FROM SOUTH LINE AND 1153 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



SCALE: 1" = 2 MILE

6/8

SHEET NO.

INTERSTATE ENGINEERING

Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
COUNTY ROAD MAP
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By: B.H.H. Project No.: S12-09-068
Checked By: D.D.K. Date: APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD

CROSS SECTIONS

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31H"
1717 FEET FROM SOUTH LINE AND 1153 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



STA. 3+00



STA. 2+00



STA. 1+00



STA. 0+00

REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS-3880
DATE: 1/03/13
NORTH DAKOTA

THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 1/03/13 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

SCALE
HORIZ 1"=80'
VERT 1"=20'

7/8
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
PAD CROSS SECTIONS
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By: B.H.H. Project No.: S12-09-068
Checked By: D.D.K. Date: APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD

WELL LOCATION SITE QUANTITIES

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT 5300 31-31H"
1717 FEET FROM SOUTH LINE AND 1153 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA

WELL SITE ELEVATION	2157.6
WELL PAD ELEVATION	2156.0

EXCAVATION	10,084
PLUS PIT	3,150
	13,234
EMBANKMENT	4,071
PLUS SHRINKAGE (30%)	1,221
	5,292
STOCKPILE PIT	3,150
STOCKPILE TOP SOIL (6")	2,974
STOCKPILE MATERIAL	1,818
DISTURBED AREA FROM PAD	3.69 ACRES

NOTE: ALL QUANTITIES ARE IN CUBIC YARDS (UNLESS NOTED)
CUT END SLOPES AT 2:1
FILL END SLOPES AT 3:1

WELL SITE LOCATION
1717' FSL
1153' FWL

8/8
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM, LLC
QUANTITIES
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By: B.H.H. Project No.: S12-09-068
Checked By: D.D.K. Date: APRIL 2012

Revision No.	Date	By	Description
REV 1	12/10/12	JJS	ADDED BH & BREAKDOWN
REV 2	12/21/12	BHH	MOVED WELL/EXPANDED PAD

Azimuths to True North
Magnetic North: 8.46°

Magnetic Field
Strength: 56651.9snT
Dip Angle: 73.03°
Date: 6/12/2012
Model: IGRF200510

OASIS PETROLEUM

Project: Indian Hills
Site: 153N-100W-31
Well: Buck Shot SWD 5300 31-31
Wellbore: Buck Shot SWD 5300 31-31
Design: Plan #2 - Slant/Horz

SITE DETAILS: 153N-100W-31

Site Centre Latitude: 48° 1' 44.700 N
Longitude: 103° 35' 58.470 W

Positional Uncertainity: 0.0
Convergence: -2.31
Local North: True





CASING DETAILS

TVD	MD	Name	Size
2170.0	2170.0	9 5/8"	9.625
5527.9	5752.0	7"	7.000

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	
4966.0	0.00	0.00	4966.0	0.0	0.0	0.00	
5736.0	77.00	14.20	5524.3	430.5	108.9	10.00	
5752.6	77.00	14.20	5528.0	446.2	112.9	0.00	
6936.3	77.00	14.20	5794.3	1564.3	395.8	0.00	



Oasis

Indian Hills
153N-100W-31
Buck Shot SWD 5300 31-31
T153N R100W SEC. 31
Buck Shot SWD 5300 31-31

Plan: Plan #2 - Slant/Horz

Standard Planning Report

28 January, 2013

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	25' KB @ 2182.0ft
Project:	Indian Hills	**MD Reference:**	25' KB @ 2182.0ft
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Buck Shot SWD 5300 31-31		
Design:	Plan #2 - Slant/Horz		

Project	Indian Hills		
Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	North Dakota Northern Zone		

Site	153N-100W-31					
Site Position:		**Northing:**	119,066.39 m	**Latitude:**		48° 1' 44.700 N
From:	Lat/Long	**Easting:**	368,900.31 m	**Longitude:**		103° 35' 58.470 W
Position Uncertainty:	0.0 ft	**Slot Radius:**	13.200 in	**Grid Convergence:**		-2.31 °

Well	Buck Shot SWD 5300 31-31						
Well Position	**+N/-S**	0.0 ft	**Northing:**	119,066.04 m	**Latitude:**	48° 1' 44.700 N
	+E/-W	27.9 ft	**Easting:**	368,908.79 m	**Longitude:**	103° 35' 58.060 W
Position Uncertainty		0.0 ft	**Wellhead Elevation:**		**Ground Level:**	2,157.0 ft

Wellbore Buck Shot SWD 5300 31-31

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	6/12/2012	8.46	73.03	56,652

Design Plan #2 - Slant/Horz

Audit Notes:

Version:		**Phase:**	PROTOTYPE	**Tie On Depth:**	0.0

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.0	0.0	0.0	14.20

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
4,966.0	0.00	0.00	4,966.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,736.0	77.00	14.20	5,524.3	430.5	108.9	10.00	10.00	0.00	14.20	
5,752.6	77.00	14.20	5,528.0	446.2	112.9	0.00	0.00	0.00	0.00	
6,936.3	77.00	14.20	5,794.3	1,564.3	395.8	0.00	0.00	0.00	0.00	

Planning Report

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	25' KB @ 2182.0ft
Project:	Indian Hills	**MD Reference:**	25' KB @ 2182.0ft
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Buck Shot SWD 5300 31-31		
Design:	Plan #2 - Slant/Horz		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
2,072.0	0.00	0.00	2,072.0	0.0	0.0	0.0	0.00	0.00	0.00
Pierre									
2,170.0	0.00	0.00	2,170.0	0.0	0.0	0.0	0.00	0.00	0.00
9 5/8"									
4,641.0	0.00	0.00	4,641.0	0.0	0.0	0.0	0.00	0.00	0.00
Greenhorn									
4,966.0	0.00	0.00	4,966.0	0.0	0.0	0.0	0.00	0.00	0.00
Start Build 10.00- KOP									
5,056.4	9.04	14.20	5,056.0	6.9	1.7	7.1	10.00	10.00	0.00
Mowry									
5,590.5	62.45	14.20	5,474.0	298.6	75.5	308.0	10.00	10.00	0.00
Dakota Top									
5,736.0	77.00	14.20	5,524.3	430.5	108.9	444.1	10.00	10.00	0.00
Start 16.6 hold at 5736.0 MD- EOC									
5,752.6	77.00	14.20	5,528.0	446.2	112.9	460.3	0.00	0.00	0.00
Start 1183.7 hold at 5752.6 MD - First Dakota Sand Top									
5,899.3	77.00	14.20	5,561.0	584.8	148.0	603.2	0.00	0.00	0.00
First Dakota Sand Base									
6,437.2	77.00	14.20	5,682.0	1,092.9	276.5	1,127.3	0.00	0.00	0.00
Second Dakota Sand Top									
6,824.0	77.00	14.20	5,769.0	1,458.2	369.0	1,504.1	0.00	0.00	0.00
Second Dakota Sand Base									
6,936.0	77.00	14.20	5,794.2	1,564.0	395.7	1,613.3	0.00	0.00	0.00
7"									
6,936.3	77.00	14.20	5,794.3	1,564.3	395.8	1,613.6	0.00	0.00	0.00
TD at 6936.3									

Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
2,170.0	2,170.0	9 5/8"	9.625	13.500
6,936.0	5,794.2	7"	7.000	8.750

Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
2,072.0	2,072.0	Pierre			
4,641.0	4,641.0	Greenhorn			
5,056.4	5,056.0	Mowry			
5,590.5	5,474.0	Dakota Top			
5,752.6	5,528.0	First Dakota Sand Top			
5,899.3	5,561.0	First Dakota Sand Base			
6,437.2	5,682.0	Second Dakota Sand Top			
6,824.0	5,769.0	Second Dakota Sand Base			

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	25' KB @ 2182.0ft
Project:	Indian Hills	**MD Reference:**	25' KB @ 2182.0ft
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Buck Shot SWD 5300 31-31		
Design:	Plan #2 - Slant/Horz		

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
4,966.0	4,966.0	0.0	0.0	Start Build 10.00- KOP
5,736.0	5,524.3	430.5	108.9	Start 16.6 hold at 5736.0 MD- EOC
5,752.6	5,528.0	446.2	112.9	Start 1183.7 hold at 5752.6 MD
6,936.3	5,794.3	1,564.3	395.8	TD at 6936.3

RYAN DIRECTIONAL SERVICES, INC.
A NABORS COMPANY

19510 Oil Center Blvd
Houston, TX 77073
Bus 281.443.1414
Fax 281.443.1676

Monday, July 08, 2013

State of North Dakota

Subject: **Surveys**

Re: **Oasis**
Buck Shot 5300 31-31
McKenzie, ND

Enclosed, please find the original and one copy of the survey performed on the above-referenced well by Ryan Directional Services, Inc. (Operator #:). Other information required by your office is as follows:

Surveyor Name	*Surveyor Title*	*Borehole Number*	*Start Depth*	*End Depth*	*Start Date*	*End Date*	*Type of Survey*	*TD Straight Line Projection*
Maldonado, Edgar	MWD Operator	O.H.	2225'	5927'	06/19/13	06/20/13	MWD	6035'
Maldonado, Edgar	MWD Operator	ST 1	4405'	6496'	06/25/13	07/01/13	MWD	6555'

A certified plat on which the bottom hole location is oriented both to the surface location and to the lease lines (or unit lines in case of pooling) is attached to the survey report. If any other information is required please contact the undersigned at the letterhead address or phone number.

Douglas Hudson

Douglas Hudson
Well Planner

RYAN DIRECTIONAL SERVICES, INC.
A NABORS COMPANY

19510 Oil Center Blvd
Houston, TX 77073
Bus 281.443.1414
Fax 281.443.1676

Monday, July 08, 2013

State of North Dakota

Subject: **Survey Certification Letter**

Re: **Oasis**
Buck Shot 5300 31-31
McKenzie, ND

I, Edgar Maldonado, certify that; I am employed by Ryan Directional Services, Inc.; that I did on the conduct or supervise the taking of the following MWD surveys:

on the day(s) of 6/19/2013 thru 6/20/2013 from a depth of 2225' MD to a depth of 5927' MD and Straight line projection to TD 6035' MD;

on the day(s) of 6/25/2013 thru 7/1/2013 from a depth of 4405' MD to a depth of 6496' MD and Straight line projection to TD 6555' MD;

that the data is true, correct, complete, and within the limitations of the tool as set forth by Ryan Directional Services, Inc.; that I am authorized and qualified to make this report; that this survey was conducted at the request of Oasis for the Buck Shot 5300 31-31; in McKenzie, ND.

Edgar Maldonado
MWD Operator
Ryan Directional Services, Inc.

Report #:	1	RYAN DIRECTIONAL SERVICES, INC. A NABORS COMPANY	Ryan Job #	6370
Date:	19-Jun-13		Kit #	23

SURVEY REPORT

Customer:	**Oasis Petroleum**	MWD Operator:	**Edgar Maldonado**
Well Name:	**Buck Shot SWD 5300 31-31**	Directional Drillers:	**RPM**
Block or Section:	**31T-153N-100W**	Survey Corrected To:	**True North**
Rig #:	**Precision Drilling 565**	Vertical Section Direction:	**14.2**
Calculation Method:	**Minimun Curvature Calculation**	Survey Correction:	**8.46**
		Temperature Forecasting Model (Chart Only):	**Logarithmic**

Survey #	MD	Inc	Azm	Temp	TVD	VS	N/S	E/W	DLS
Tie in to Gyro Surveys									
Tie In	**2225**	**0.00**	**0.00**	**0.00**	**2225.00**	**0.00**	**0.00**	**0.00**	**0.00**
1	2254	0.50	132.90	80.00	2254.00	-0.06	-0.09	0.09	1.72
2	2344	0.50	162.50	86.00	2344.00	-0.58	-0.73	0.50	0.28
3	2433	0.50	180.80	87.00	2432.99	-1.29	-1.49	0.61	0.18
4	2523	0.60	184.10	89.00	2522.99	-2.14	-2.35	0.57	0.12
5	**2612**	**0.60**	**173.80**	**91.00**	**2611.98**	**-3.03**	**-3.28**	**0.59**	**0.12**
6	2702	0.60	173.10	93.00	2701.98	-3.91	-4.21	0.70	0.01
7	2792	0.50	179.10	96.00	2791.97	-4.73	-5.07	0.76	0.13
8	2881	0.60	198.20	98.00	2880.97	-5.57	-5.91	0.62	0.23
9	2971	0.80	199.00	100.00	2970.96	-6.67	-6.95	0.27	0.22
10	**3060**	**0.90**	**204.40**	**102.00**	**3059.95**	**-7.98**	**-8.17**	**-0.22**	**0.14**
11	3150	1.00	217.70	104.00	3149.94	-9.39	-9.44	-1.00	0.27
12	3240	1.00	208.50	105.00	3239.93	-10.87	-10.75	-1.85	0.18
13	3329	0.90	208.20	107.00	3328.92	-12.30	-12.05	-2.55	0.11
14	3419	0.80	208.90	111.00	3418.91	-13.60	-13.22	-3.19	0.11
15	**3508**	**0.70**	**202.30**	**113.00**	**3507.90**	**-14.74**	**-14.27**	**-3.70**	**0.15**
16	3598	0.70	203.10	114.00	3597.89	-15.82	-15.28	-4.12	0.01
17	3688	0.60	206.60	114.00	3687.89	-16.83	-16.21	-4.55	0.12
18	3777	0.60	207.30	116.00	3776.88	-17.74	-17.04	-4.97	0.01
19	3867	0.60	214.60	118.00	3866.88	-18.64	-17.84	-5.45	0.08
20	**3957**	**0.60**	**217.90**	**118.00**	**3956.87**	**-19.51**	**-18.60**	**-6.01**	**0.04**
21	4046	0.60	215.00	120.00	4045.87	-20.37	-19.35	-6.56	0.03
22	4136	0.50	219.10	118.00	4135.86	-21.17	-20.04	-7.08	0.12
23	4225	0.40	219.70	120.00	4224.86	-21.80	-20.59	-7.53	0.11
24	4315	0.30	216.40	122.00	4314.86	-22.30	-21.02	-7.87	0.11
25	**4405**	**0.20**	**213.30**	**123.00**	**4404.86**	**-22.67**	**-21.34**	**-8.09**	**0.11**
26	4494	0.10	212.60	123.00	4493.86	-22.89	-21.53	-8.22	0.11
27	4584	0.20	231.50	123.00	4583.86	-23.09	-21.70	-8.38	0.12
28	4673	0.30	275.40	125.00	4672.86	-23.25	-21.77	-8.74	0.23
29	4763	0.30	293.40	127.00	4762.85	-23.25	-21.66	-9.19	0.10
30	**4852**	**0.60**	**299.10**	**127.00**	**4851.85**	**-23.09**	**-21.34**	**-9.81**	**0.34**
31	4942	0.90	287.40	129.00	4941.84	-22.93	-20.90	-10.90	0.37
32	5032	1.70	267.70	129.00	5031.82	-23.27	-20.74	-12.90	1.01
33	5121	0.70	245.80	127.00	5120.80	-23.98	-21.01	-14.72	1.22
34	5211	0.40	218.30	129.00	5210.80	-24.61	-21.49	-15.42	0.43
35	**5301**	**0.50**	**165.10**	**129.00**	**5300.79**	**-25.24**	**-22.11**	**-15.51**	**0.46**
36	5390	0.60	105.20	127.00	5389.79	-25.59	-22.61	-14.96	0.62
37	5480	0.70	92.20	123.00	5479.78	-25.48	-22.75	-13.96	0.20
38	5569	0.80	88.40	123.00	5568.78	-25.20	-22.76	-12.79	0.13
39	5659	0.70	78.30	122.00	5658.77	-24.79	-22.63	-11.63	0.18
40	**5748**	**1.00**	**78.70**	**122.00**	**5747.76**	**-24.22**	**-22.37**	**-10.33**	**0.34**
41	5838	0.80	83.40	123.00	5837.75	-23.66	-22.14	-8.94	0.24
42	5927	0.80	76.00	123.00	5926.74	-23.14	-21.92	-7.72	0.12
Projection	6035	0.80	76.00	123.00	6034.73	-22.43	-21.55	-6.25	0.00

Report #: 2

Date: 19-Jun-13

RYAN DIRECTIONAL SERVICES, INC.

A NABORS COMPANY

Ryan Job # 6370

Kit # 23

SURVEY REPORT

Customer:	Oasis Petroleum	MWD Operator:	Edgar Maldonado
Well Name:	Buck Shot SWD 5300 31-31	Directional Drillers:	RPM
Block or Section:	31T-153N-100W	Survey Corrected To:	True North
Rig #:	Precision Drilling 565	Vertical Section Direction:	14.2
Calculation Method:	Minimun Curvature Calculation	Survey Correction:	8.46
		Temperature Forecasting Model (Chart Only):	Logarithmic

Survey #	MD	Inc	Azm	Temp	TVD	VS	N/S	E/W	DLS
Tie in to Gyro Surveys									
Tie In	**4405**	**0.20**	**213.30**	**123.00**	**4404.86**	**-22.67**	**-21.33**	**-8.10**	**0.11**
1	4493	0.30	184.30	100.00	4492.86	-23.04	-21.69	-8.20	0.18
2	4582	0.90	344.00	114.00	4581.86	-22.66	-21.25	-8.41	1.33
3	4672	5.10	19.80	114.00	4671.72	-18.07	-16.80	-7.25	4.89
4	4762	4.90	18.20	116.00	4761.37	-10.25	-9.39	-4.70	0.27
5	**4851**	**4.80**	**15.90**	**116.00**	**4850.06**	**-2.74**	**-2.20**	**-2.49**	**0.25**
6	4941	4.40	12.50	118.00	4939.77	4.48	4.80	-0.71	0.54
7	4986	5.80	27.30	118.00	4984.59	8.42	8.50	0.71	4.24
8	5030	11.90	23.60	118.00	5028.04	15.06	14.64	3.55	13.92
9	5075	16.60	26.40	120.00	5071.65	25.93	24.66	8.26	10.55
10	**5120**	**16.50**	**27.10**	**120.00**	**5114.78**	**38.44**	**36.10**	**14.03**	**0.50**
11	5165	15.90	27.80	122.00	5158.00	50.66	47.24	19.82	1.40
12	5210	15.90	27.70	116.00	5201.28	62.65	58.15	25.56	0.06
13	5254	20.40	24.30	105.00	5243.08	76.06	70.49	31.52	10.50
14	5299	23.50	19.70	107.00	5284.81	92.72	86.09	37.77	7.87
15	**5344**	**27.40**	**13.80**	**111.00**	**5325.44**	**112.02**	**104.60**	**43.27**	**10.33**
16	5389	29.30	13.00	114.00	5365.05	133.38	125.38	48.22	4.31
17	5433	32.00	13.10	116.00	5402.90	155.81	147.23	53.28	6.14
18	5478	36.90	12.40	118.00	5439.99	181.25	172.06	58.89	10.92
19	5523	41.50	11.20	120.00	5474.86	209.65	199.89	64.69	10.36
20	**5568**	**42.70**	**11.40**	**120.00**	**5508.24**	**239.78**	**229.47**	**70.60**	**2.68**
21	5613	46.50	12.20	120.00	5540.28	271.35	260.40	77.07	8.54
22	5657	50.90	12.60	122.00	5569.31	304.38	292.67	84.17	10.02
23	5702	57.90	12.10	123.00	5595.49	340.92	328.39	91.98	15.58
24	5747	62.10	12.50	123.00	5617.99	379.87	366.46	100.29	9.36
25	**5792**	**63.10**	**13.10**	**123.00**	**5638.70**	**419.80**	**405.42**	**109.14**	**2.52**
26	5837	68.40	12.80	125.00	5657.17	460.81	445.39	118.33	11.79
27	5882	70.10	13.70	125.00	5673.11	502.88	486.35	127.97	4.22
28	5926	71.70	14.80	125.00	5687.51	544.46	526.65	138.21	4.34
29	5971	71.50	15.30	125.00	5701.72	587.15	567.88	149.30	1.14
30	**6016**	**69.80**	**15.10**	**125.00**	**5716.63**	**629.60**	**608.85**	**160.43**	**3.80**
31	6061	69.90	14.90	125.00	5732.13	671.84	649.66	171.36	0.47
32	6106	70.40	15.10	127.00	5747.41	714.17	690.54	182.32	1.19
33	6150	70.60	15.30	127.00	5762.09	755.64	730.57	193.19	0.62
34	6241	70.70	14.90	147.00	5792.25	841.48	813.46	215.56	0.43
35	**6337**	**69.60**	**16.10**	**140.00**	**5824.84**	**931.75**	**900.47**	**239.69**	**1.64**
36	6432	69.80	16.40	140.00	5857.80	1020.80	986.01	264.62	0.36
37	6496	69.80	16.70	138.00	5879.90	1080.81	1043.59	281.73	0.44
Projection	6555	69.80	16.70	138.00	5900.28	1136.13	1096.62	297.64	0.00

SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4
INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

RECEIVED MAY 2013 ND OIL & GAS DIVISION

Well File No. **90244**

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- [x] Notice of Intent — Approximate Start Date: **May 22, 2013**
- [ ] Report of Work Done — Date Work Completed:
- [ ] Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

- [ ] Drilling Prognosis
- [ ] Redrilling or Repair
- [ ] Casing or Liner
- [ ] Plug Well
- [ ] Supplemental History
- [ ] Temporarily Abandon
- [x] Other **Suspension of Drilling**
- [ ] Spill Report
- [ ] Shooting
- [ ] Acidizing
- [ ] Fracture Treatment
- [ ] Change Production Method
- [ ] Reclamation

Well Name and Number					
Buck Shot SWD 5300 31-31					
Footages		Qtr-Qtr	Section	Township	Range
1717 F S L	1153 F W L	NWSW	~~21~~ 31	153 N	100 W
Field	Pool		County		
Baker	Bakken		McKenzie		

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s)			
Advanced Energy Services			
Address	City	State	Zip Code

DETAILS OF WORK

Oasis Petroleum North America LLC requests permission for suspension of drilling for up to ~~90~~ 45 days for the referenced well under NDAC 43-02-03-55. Oasis Petroleum North America LLC intends to drill the surface hole with freshwater based drilling mud and set surface casing with a small drilling rig and move off within 3 to 5 days. The casing will be set at a depth pre-approved by the NDIC per the Application for Permit to Drill NDAC 43-02-03-21. No saltwater will be used in the drilling and cementing operations of the surface casing. Once the surface casing is cemented, a plug or mechanical seal will be placed at the top of the casing to prevent any foreign matter from getting into the well. A rig capable of drilling to TD will move onto the location within the ~~90~~ 45 days previously outlined to complete the drilling and casing plan as per the APD. The undersigned states that this request for suspension of drilling operations in accordance with the Subsection 4 of Section 43-02-03-55 of the NDAC, is being requested to take advantage of the cost savings and time savings of using an initial rig that is smaller than the rig necessary to drill a well to total depth~~, but is not intended to alter or extend the terms and conditions of, or suspend any obligation under, any oil and gas lease with acreage in or under the spacing or drilling unit for the above-referenced well~~. Oasis Petroleum North America LLC understands NDAC 43-02-03-31 requirements regarding confidentiality pertaining to this permit. The drilling pit will be fenced immediately after construction if the well pad is located in a pasture (NDAC 43-02-03-19 & 19.1). Oasis Petroleum North America LL will plug and abandon the well and reclaim the well site if the well is not drilled by the larger rotary rig within ~~90~~ 45 days after spudding the well with the smaller drilling rig.

Company		Telephone Number
Oasis Petroleum North America LLC		(281) 404-9563
Address		
1001 Fannin, Suite 1500		
City	State	Zip Code
Houston	TX	77002
Signature	Printed Name	
[signature]	Heather McCowan	
Title	Date	
Regulatory Assistant	May 22, 2013	
Email Address		
hmccowan@oasispetroleum.com		

FOR STATE USE ONLY

[ ] Received	[x] Approved
Date	05-23-2013
By	[signature]
Title	David Burns ~~Engineering Tech.~~

Oasis must contact NDIC Inspector Richard Dunn 701-770-3554 with spud & TD

SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

JAN 2013
RECEIVED
ND OIL & GAS DIVISION

Well File No. 90244

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- [x] Notice of Intent — Approximate Start Date: June 1, 2012
- [ ] Report of Work Done — Date Work Completed:
- [ ] Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

- [ ] Drilling Prognosis
- [ ] Redrilling or Repair
- [ ] Casing or Liner
- [ ] Plug Well
- [ ] Supplemental History
- [ ] Temporarily Abandon
- [x] Other: Expand pad and move surface location
- [ ] Spill Report
- [ ] Shooting
- [ ] Acidizing
- [ ] Fracture Treatment
- [ ] Change Production Method
- [ ] Reclamation

Well Name and Number: Buck Shot SWD 5300 31-31

Footages		Qtr-Qtr	Section	Township	Range
1710 F S L	1125 F W L	NWSW	21	153 N	100 W

Field	Pool	County
Baker	Dakota Group	McKenzie

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s):

Address	City	State	Zip Code

DETAILS OF WORK

Oasis Petroleum respectfully requests to make the following changes to the Buck Shot SWD 5300 31-31 permitted location:

Expand the drilling pad to allow for rig flexibility
Surface hole changed to: 1717' FSL & 1153' FWL

Please find attached revised directional plan.

Company	Telephone Number
Oasis Petroleum North America	(281) 404-9491

Address: 1001 Fannin Suite 1500

City	State	Zip Code
Houston	TX	77002

Signature: [signature] — Printed Name: Brandi Terry
Title: Regulatory Specialist — Date: January 15, 2013
Email Address: bterry@oasispetroleum.com

FOR STATE USE ONLY

- [ ] Received
- [x] Approved

Date: 1-18-2013
By: [signature]
Title: UNDERGROUND INJECTION SUPERVISOR

Oasis Petroleum
Well Summary
Buck Shot SWD 5300 31-31
Section 31 T153N R100W
McKenzie County, ND

SURFACE CASING AND CEMENT DESIGN

							Make-up Torque (ft-lbs)		
Size	**Interval**	**Weight**	**Grade**	**Coupling**	**I.D.**	**Drift**	**Minimum**	**Optimum**	**Max**
9-5/8"	0' to 2,170'	36	J-55	LTC	8.921"	8.765"	3400	4530	5660

Interval	**Description**	**Collapse**	**Burst**	**Tension**	**Cost per ft**
		(psi) a	(psi) b	(1000 lbs) c	
0' to 2,170'	9-5/8", 36#, J-55, LTC, 8rd	2020 / 1.99	3520 / 3.47	453 / 2.71	

API Rating & Safety Factor

a) Based on full casing evacuation with 9.0 ppg fluid on backside (2,170' setting depth).
b) Burst pressure based on 9 ppg fluid with no fluid on backside (2,170' setting depth).
c) Based on string weight in 9.0 ppg fluid at 2,170' TVD plus 100k# overpull. (Buoyed weight equals 67k lbs.)

Cement volumes are based on 9-5/8" casing set in 13-1/2" hole with 55% excess to circulate cement back to surface. Mix and pump the following slurry.

Pre-flush (Spacer): **20 bbls** fresh water

Lead Slurry: **460 sks** (238 bbls) Conventional system with 94 lb/sk cement, 4% extender, 2% expanding agent, 2% CaCl2 and 0.25 lb/sk lost circulation control agent

Tail Slurry: **300 sks** (61 bbls) Conventional system with 94 lb/sk cement, 3% NaCl, and 0.25 lb/sk lost circulation control agent

Oasis Petroleum
Well Summary
Buck Shot SWD 5300 31-31
Section 31 T153N R100W
McKenzie County, ND

INTERMEDIATE CASING AND CEMENT DESIGN

Intermediate Casing Design

Size	Interval	Weight	Grade	Coupling	I.D.	Drift	Make-up Torque (ft-lbs) Minimum	Optimum	Max
7"	0' – 5,965'	26	L-80	LTC	6.276"	6.151"	3900	4900	5900

**Special Drift

Interval	Description	Collapse (psi) a	Burst (psi) b	Tension (1000 lbs) c
0' – 5,965'	7", 26#, L-80, LTC, 8rd	5410 / 2.19	7240 / 2.94	511 / 2.46

API Rating & Safety Factor

a) Collapse pressure based on full casing evacuation with 10 ppg fluid on backside (5,565' setting depth).
b) Burst pressure based on 5,000 psi max stimulation pressure plus 10.0 ppg fluid inside casing with 9.0 ppg fluid on backside (5,565' setting depth).
c) Based on string weight in 10 ppg fluid at 5,965' MD plus 100k# overpull. (Buoyed weight equals 126k lbs.)

Cement volumes are estimates based on 7" casing set in an 8-3/4" hole with 30% excess.

Pre-flush (Spacer): **20 bbls CW8 System**
20 bbls fresh water

Lead Slurry: **180 sks** (83 bbls) 11.5 lb/gal LiteCRETE with 27.005 lb/sk Extender, 10% NaCl, 0.40% Dispersant, 0.25% Retarder, 0.20% Anti-foam, 0.10% Retarder, 0.25 lb/sk lost circulation control agent

Tail Slurry: **260 sks** (158 bbls) 15.6 lb/gal conventional system with 94 lb/sk cement, 10% NaCl, 35% Silica, 0.20% dispersant, 0.40% fluid loss agent, 0.10% retarder, and 0.25 lb/sk lost circulation control agent

Oasis

Indian Hills
153N-100W-31
Buck Shot SWD 5300 31-31
T153N R100W SEC. 31
Buck Shot SWD 5300 31-31

Plan: Plan #1

Standard Planning Report

04 January, 2013

Planning Report

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	25' KB @ 2182.0ft
Project:	Indian Hills	**MD Reference:**	25' KB @ 2182.0ft
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Buck Shot SWD 5300 31-31		
Design:	Plan #1		

Project	Indian Hills		
Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	North Dakota Northern Zone		

Site	153N-100W-31						
Site Position:			**Northing:**	119,066.39 m	**Latitude:**	48° 1' 44.700 N
From:	Lat/Long		**Easting:**	368,900.31 m	**Longitude:**	103° 35' 58.470 W
Position Uncertainty:		0.0 ft	**Slot Radius:**	13.200 in	**Grid Convergence:**	-2.31 °

Well	Buck Shot SWD 5300 31-31					
Well Position	**+N/-S**	0.0 ft	**Northing:**	119,066.04 m	**Latitude:**	48° 1' 44.700 N
	+E/-W	27.9 ft	**Easting:**	368,908.79 m	**Longitude:**	103° 35' 58.060 W
Position Uncertainty		0.0 ft	**Wellhead Elevation:**		**Ground Level:**	2,157.0 ft

Wellbore Buck Shot SWD 5300 31-31

Magnetics	**Model Name**	**Sample Date**	**Declination (°)**	**Dip Angle (°)**	**Field Strength (nT)**
	IGRF200510	6/12/2012	8.46	73.03	56,652

Design Plan #1

Audit Notes:

Version: **Phase:** PROTOTYPE **Tie On Depth:** 0.0

Vertical Section:	**Depth From (TVD) (ft)**	**+N/-S (ft)**	**+E/-W (ft)**	**Direction (°)**
	0.0	0.0	0.0	0.00

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,965.0	0.00	0.00	5,965.0	0.0	0.0	0.00	0.00	0.00	0.00	

Planning Report

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	25' KB @ 2182.0ft
Project:	Indian Hills	**MD Reference:**	25' KB @ 2182.0ft
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Buck Shot SWD 5300 31-31		
Design:	Plan #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
2,022.0	0.00	0.00	2,022.0	0.0	0.0	0.0	0.00	0.00	0.00
Pierre									
2,125.0	0.00	0.00	2,125.0	0.0	0.0	0.0	0.00	0.00	0.00
9 5/8"									
4,629.0	0.00	0.00	4,629.0	0.0	0.0	0.0	0.00	0.00	0.00
Greenhorn									
5,044.0	0.00	0.00	5,044.0	0.0	0.0	0.0	0.00	0.00	0.00
Mowry									
5,462.0	0.00	0.00	5,462.0	0.0	0.0	0.0	0.00	0.00	0.00
Dakota Top									
5,516.0	0.00	0.00	5,516.0	0.0	0.0	0.0	0.00	0.00	0.00
First Dakota Sand Top									
5,549.0	0.00	0.00	5,549.0	0.0	0.0	0.0	0.00	0.00	0.00
First Dakota Sand Base									
5,670.0	0.00	0.00	5,670.0	0.0	0.0	0.0	0.00	0.00	0.00
Second Dakota Sand Top									
5,757.0	0.00	0.00	5,757.0	0.0	0.0	0.0	0.00	0.00	0.00
Second Dakota Sand Base									
5,795.0	0.00	0.00	5,795.0	0.0	0.0	0.0	0.00	0.00	0.00
Third Dakota Sand Top									
5,815.0	0.00	0.00	5,815.0	0.0	0.0	0.0	0.00	0.00	0.00
Third Dakota Sand Base									
5,837.0	0.00	0.00	5,837.0	0.0	0.0	0.0	0.00	0.00	0.00
Forth Dakota Sand Top									
5,915.0	0.00	0.00	5,915.0	0.0	0.0	0.0	0.00	0.00	0.00
Forth Dakota Sand Base									
5,965.0	0.00	0.00	5,965.0	0.0	0.0	0.0	0.00	0.00	0.00
TD at 5965.0 - 7"									

Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
2,125.0	2,125.0	9 5/8"	9.625	13.500
5,965.0	5,965.0	7"	7.000	8.750

Planning Report

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	25' KB @ 2182.0ft
Project:	Indian Hills	**MD Reference:**	25' KB @ 2182.0ft
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Buck Shot SWD 5300 31-31		
Design:	Plan #1		

Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
2,022.0	2,022.0	Pierre			
4,629.0	4,629.0	Greenhorn			
5,044.0	5,044.0	Mowry			
5,462.0	5,462.0	Dakota Top			
5,516.0	5,516.0	First Dakota Sand Top			
5,549.0	5,549.0	First Dakota Sand Base			
5,670.0	5,670.0	Second Dakota Sand Top			
5,757.0	5,757.0	Second Dakota Sand Base			
5,795.0	5,795.0	Third Dakota Sand Top			
5,815.0	5,815.0	Third Dakota Sand Base			
5,837.0	5,837.0	Forth Dakota Sand Top			
5,915.0	5,915.0	Forth Dakota Sand Base			

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
5,965.0	5,965.0	0.0	0.0	TD at 5965.0

DRILLING PLAN

PROSPECT/FIELD	[illegible] Vertical Dakota Water Disposal Well	COUNTY/STATE	McKenzie Co., ND
OPERATOR	Oasis Petroleum	RIG	[illegible]
WELL NAME	[illegible]		
LOCATION	[illegible]	Surface Location (survey plat):	1717 fsl / 1153 fwl
EST. T.D.	5,965		

GROUND ELEV: 2157 Finished Pad Elev. **Sub Hieght:** 25
KB ELEV: 2182

PROGNOSIS: Based on 2,182' KB(est)

MARKER	DEPTH (Surf Loc)	DATUM (Surf Loc)
Pierre	2,070	112
Greenhorn	4,639	(2,457)
Mowry	5,054	(2,872)
Dakota Top	5,472	(3,290)
First Dakota Sand Top	5,526	(3,344)
First Dakota Sand Base	5,559	(3,377)
Second Dakota Sand Top	5,680	(3,498)
Second Dakota Sand Base	5,767	(3,585)
Third Dakota Sand Top	5,805	(3,623)
Third Dakota Sand Base	5,825	(3,643)
Forth Dakota Sand Top	5,847	(3,665)
Forth Dakota Sand Base/Swift	5,925	(3,743)

LOGS: Type / Interval
OH Logs: Triple Combo up to casing, GR/Res to BSC; GR to surf
CBL/GR: Above top of cement/GR to base of casing

DEVIATION: None

DST'S: None planned

CORES: None planned

MUDLOGGING: None planned

BOP: 3k blind, pipe & annular

Max. Anticipated BHP: [illegible]

Surface Formation: *Glacial till*

MUD:	Interval		Type	WT	Vis	WL	Remarks
Surface	0' -	2,170'	FW/Gel Lime Sweeps	8.6 - 8.9	28-34	NC	Circ Mud Tanks
Straight Hole	2,170' -	#REF!	Invert	8.8-9.5	40-60	HTHP	Circ Mud Tanks

CASING:	Size	Wt ppf	Hole	Depth	Cement	WOC	Remarks
Surface:	9 5/8"	36	13 1/2"	2,170	To surface	12 hours	
Intermediate:	7"	26	8 3/4"	5,965	2,125	12 hours	

PROBABLE PLUGS, IF REQ'D:

OTHER:	MD	TVD	FNL/FSL	FEL/FWL	S-T-R	AZI
Surface:	2,170	2,170	1717' FSL	1153' FWL	T152N-R101W-Sec. 31	N/A
Csg Pt/TD:	5,965	5,965	1717' FSL	1153' FWL	T152N-R101W-Sec. 31	N/A

Comments:

MWD survey every 100'
Drill to TD and log

Reserve pit fluids will be hauled to the nearest disposal site/Reserve pit solids will be solidified and reclaimed in the lined reserve pit

OASIS PETROLEUM

Geology: ANELSON 06-12-2012 **Engineering:** M. Brown 1-3-2013

PERMIT FOR FLUID INJECTION

OPERATOR: Oasis Petroleum North America LLC

ADDRESS: 1001 Fannin, Suite 1500 Houston, TX 77002

WELL NAME & NO.: Buck Shot SWD 5300 31-31

LOCATION: NWSW Section 31, T153N, R100W McKenzie, ND

AUTHORIZED INJECTION ZONE: Dakota Group

UNDERGROUND INJECTION CONTROL (UIC) NO.: W0346S0820D

WELL FILE NO.: 90244

PERMIT DATE: September 5, 2012

The operator shall notify the North Dakota Industrial Commission ("Commission") at least 24 hours prior to plugging back and converting said well to a saltwater disposal well. This permit is conditioned upon the operator complying with the provisions set forth in Chapter 43-02-05, Chapter 43-02-03, any other applicable rules or orders of the Commission, and the following stipulations:

(1) A pressure test to 100 psi over the Permitted Maximum Injection Pressure must be performed on the pipeline between the off site tank battery for the BWL SWD 5201 11-3, and the Buck Shot SWD #5300 31-31 disposal well prior to injecting fluids and annually thereafter.

(2) The operator shall obtain approval on plug-back procedure prior to converting said well to a saltwater disposal well.

(3) The injection interval shall be isolated by cement and verified by a cement bond log prior to injecting fluids.

(4) Injection shall be through tubing and packer set within 100 feet of the top perforation.

(5) A Commission Field Inspector must witness a satisfactory mechanical integrity test on the tubing-casing annulus prior to injecting fluids.

(6) Accurate pressure gauges shall be placed on the tubing and on the tubing-casing annulus.

(7) Written notice must be given of the date of first injection immediately and of any discontinuance within ten days. Written notice must also be given of the date injection

recommences.

(8) All fluids injected shall be metered or measured using an approved method.

(9) The operator is only authorized to inject Class II fluids into said well. Class II fluids are generally defined as follows:

a. Produced water from oil and gas production;
b. Waste fluids from actual drilling operations;
c. Used workover, completion, and stimulation fluids recovered from production, injection and exploratory wells;
d. Waste fluids from circulation during well cementing;
e. Pigging fluids from cleaning of collection and injection lines within the field;
f. Enhanced recovery waters including fresh water makeup and other waters containing chemicals for the purpose of enhanced recovery;
g. Gases used for enhanced recovery/pressure maintenance of production reservoirs;
h. Brine reject from water softeners associated with enhanced recovery;
i. Waste oil and fluids from clean up within the oil field;
j. Waste water from gas plants which are an integral part of production operations unless those waters are classified as hazardous waste at the time of injection.

(10) Two copies of all logs run hereinafter and a Sundry Notice (Form 4) detailing the conversion of this well must be submitted to the Commission within 30 days after the completion of the conversion. The logs shall be submitted as one paper copy and one digital LAS (log ASCII) formatted copy, or a format approved by the director. The Sundry Notice shall include, but not be limited to, the following information: work completed and depths to plug back well, plug back depth, details of any isolation squeezes, perforated interval, packer type and depth, tubing size and type, and any other remedial work done as well as the dates the work was performed

(11) The operator shall report any noncompliance with regulations or permit conditions within 24 hours followed by a written explanation within five days.

(12) Approval shall be obtained prior to attempting any remedial work to the casing strings.

(13) Following any remedial work done to this well over the life of this well, a Sundry Notice (Form 4) must be submitted detailing the work done. This report shall include the reason for the workover, the work done, dates, size and type of tubing, type and location of packer, result of pressure test, and any other pertinent data.

(14) Following the completion of any remedial work, the Director is authorized to order further mechanical integrity tests or other remedial work as deemed necessary to insure the mechanical integrity of the well and to prevent the movement of injected fluids into an underground source of drinking water or a zone other than authorized herein.

(15) The operator shall report monthly, regardless of the status of the operations, the amount of any fluid injected, the sources thereof, and the average injection pressure. The reports (Forms 16 and 16A) shall be filed with the Director on or before the fifth day of the second month following that in which injection occurred or could have occurred.

(16) If oil is recovered from the disposal operations, the operator shall report monthly, regardless of the status of the operations, the amount of oil recovered and sold, and the purchaser of said oil. The reports (Form 5 SWD) shall be filed with the Director on or before the 1st day of the second succeeding month.

(17) The well and injection system shall be kept under continuing surveillance.

(18) Injection operations shall cease immediately if so directed by the Director or one of his

representatives.

(19) The operator shall conduct tests and install monitoring equipment as prescribed by the Director to verify the integrity of the surface facility, gathering system and injection well and to insure that the surface and subsurface potable waters will be protected.

(20) All fires, breaks, leaks, spills, or other accidents of this nature shall be reported to the Oil and Gas Division orally within 24 hours after the discovery and followed by a report within 10 days. The report shall include, but not be limited to, the following information:

a. Operator of facility.
b. Name and number of facility.
c. Exact location of accident.
d. Date of occurrence.
e. Date of cleanup.
f. Amount and type of each fluid involved.
g. Amount of each fluid recovered.
h. Steps taken to remedy the situation.
i. Cause of the accident.
j. Action taken to prevent reoccurrence.
k. Signature and title of company representative.
l. Telephone number of company representative.

(21) The Director is hereby authorized to issue administrative orders to include such other terms and conditions as may be necessary to insure proper compliance with the provisions of Chapter 38-08 of the North Dakota Century Code and Chapter 43-02-05 and 43-02-03 of the North Dakota Administrative Code. The Director is further authorized to immediately order the well shut-in if mechanical failure or downhole problems indicate that injected fluids are, or may be, moving into a zone other than authorized herein, or if the operator of the well fails to comply with the statutes, rules, orders of the Commission or written or oral directives of the Commission or its staff.

(22) Unless the well is converted to a saltwater disposal well by September 5, 2013, this permit shall expire and be of no further force and effect.

(23) If the authorized injection zone is plugged and abandoned, this permit shall expire and be of no further force and effect.

This permit is effective the date set forth below and is transferable only upon approval of the Commission.

Dated this 5th day of September, 2012.

North Dakota Industrial Commission
Oil and Gas Division
Lynn D. Helms
Director

By: ______________________
Stephen Fried
UIC Supervisor

UIC PERMIT CHECKLIST

Well File No.
90244

Operator		Well Name	Date Received
Oasis Petroleum North America LLC		Buck Shot SWD #5300 31-31	June 25, 2012

Location of Well	Qtr-Qtr	Section	Township	Range	County
1710 F S L 1125 F W L	NWSW	31	153 N	100 W	McKenzie

Field	Current Pool	Current Status
Baker	Dakota Group	Proposed

Logs on File	Top of Cement	TOC Determined By and Date
2BRun	2BDetermined Feet	☑ CBL ☐ Temp ☐ Calc

Injection Zone	Top	Confining Zone	Thickness
Dakota Group	5462 Feet	Skull Creek	250 Feet

X 1. Operator and well on bond as listed.

X 2. Completed Form 14.

Estimated frac pressure of confining zone. 4369 psi, gradient 0.8 psi/ft.

Maximum injection rate and pressure. 5000 bpd @ 1500 psi.

K_{FH}base 2000 Feet.

X 3. Lithology of proposed injection zone and confining zones.*

X 4. Map of area of review.

X 5. Name and location of wells in area of review. **F(20314) Well needs pipeline test.**

X 6. Corrective action on wells in area of review.

X 7. Injection program.*

X 8. X a. Analysis from state certified lab of two nearest fresh water wells.*

NA b. For units listed below: name and location of two nearest fresh water wells.

NA c. For units listed below: analysis from state certified lab of any new fresh water wells.

X 9. Analysis from state certified lab of injection fluid.*

X 10. List of source wells.*

X 11. Landowner description within area of review.*

X 12. Certification of notification of landowners and letter sent.*

NA 13. Logs and test data if not previously submitted.

X 14. Drawing of current* and proposed well bore and surface construction.*

X 15. Dike Schematic

X 16. Traffic Flow Diagram

X 17. Sundry detailing conversion procedure.

X 18. Form 1

Date Landowner Notified
June 19, 2012

Note: " * " indicates that the item is not required for EOR wells in the Cedar Creek, Cedar Hills North, Medicine Pole Hills South, Mohall, and Wiley units.

Hearing

Hearing Date	Case No.	Order No.	Permit Date	UIC Number
July Docket	18254	20523	September 5, 2012	W0346S0820D

Administrative

Order No. Allowing Injection	Permit Date	UIC Number
NA	NA	NA

Permit Approved By (Initials)
Stephen Fried SJF

APPLICATION FOR INJECTION - FORM 14

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 18669 (02-2011)

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM. PLEASE SUBMIT THE ORIGINAL AND TWO COPIES.
APPROVAL MUST BE OBTAINED BEFORE WORK COMMENCES.

Permit Type: ☐ Enhanced Recovery ☑ Saltwater Disposal ☐ Gas Storage	Injection Well Type: ☐ Converted ☑ Newly Drilled
Commercial SWD	☐ Yes ☑ No
Operator	**Oasis Petroleum North America LLC**
Telephone Number	**(281) 404-9500**
Will Oil be Skimmed?	☑ Yes ☐ No
Address	**1001 Fannin, Suite 1500**
City	**Houston**
State	**TX**
Zip Code	**77002**
Well Name and Number	**Buck Shot SWD 5300 31-31**
Field or Unit	**Camp**

LOCATIONS

	Footages		Qtr-Qtr	Section	Township	Range	County
At Surface	1710 F S L	1125 F W L	NWSW	31	153 N	100 W	McKenzie
Bottom Hole Location	1710 F S L	1125 F W L	NWSW	31	153 N	100 W	McKenzie

Geologic Name of Injection Zone	**Dakota Group**
Top	**5462** Feet
Injection Interval	**5516-5915** Feet
Geologic Name of Top Confining Zone	**Skull Creek**
Thickness	**250** Feet
Geologic Name of Bottom Confining Zone	**Swift**
Thickness	**460** Feet
Bottom Hole Fracture Pressure of the Top Confining Zone	**4369** PSI
Gradient	**0.80** PSI/Ft
Estimated Average Injection Rate and Pressure	**3000 BPD** @ **1000** PSI
Estimated Maximum Injection Rate and Pressure	**5000 BPD** @ **1500** PSI
Geologic Name of Lowest Known Fresh Water Zone	**Fox Hills**
Depth to Base of Fresh Water Zone	**2060** Feet
Total Depth of Well (MD & TVD)	**5965 MD/TVD** Feet
Logs Previously Run on Well	**Triple combo through Mowry, GR/Res to BSC, GR to surface to be run after TD**

CASING, TUBING, AND PACKER DATA (Check If Existing)

NAME OF STRING	SIZE	WEIGHT (Lbs/Ft)	SETTING DEPTH	SACKS OF CEMENT	TOP OF CEMENT	TOP DETERMINED BY
Surface ☑	9 5/8"	36	2135	673	Surface	Visual Observation
Intermediate ☐						
Long String ☑	7"	26	5965	440	2135	CBL

				TOP	BOTTOM	SACKS OF CEMENT
Liner ☐						

				TYPE
Proposed Tubing	4 1/2"	10.5	5465	J-55 Sealite Coated

Proposed Packer Setting Depth: **5465** Feet	Model: **Internally coated Baker lockset**	☑ Compression ☐ Permanent ☐ Tension

FOR STATE USE ONLY

Permit Number and Well File Number	90244
UIC Number	W0346S0820D
Approval Date	9-5-2012
By	Stephen Fried
Title	UNDERGROUND INJECTION SUPERVISOR

COMMENTS

I hereby swear or affirm that the information provided is true, complete and correct as determined from all available records.			Date **August 14, 2012**
Signature	Printed Name **Tommy Thompson**	Title **Sr Facilities Engineer**	

Above Signature Witnessed By

Witness Signature	Witness Printed Name	Witness Title
	Brandi Terry	**Regulatory Specialist**

Instructions

1. Attach a list identifying all attachments.
2. The operator, well name and number, field or unit, well location, and any other pertinent data shall coincide with the official records on file with the Commission. If it does not, an explanation shall be given.
3. If an injection well is to be drilled, an Application for Permit to Drill - Form 1 (SFN 4615) shall also be completed and accompanied by a plat prepared by a registered surveyor and a drilling fee.
4. Attach a lithologic description of the proposed injection zone and the top and bottom confining zones.
5. Attach a plat depicting the area of review (1/4-mile radius) and detailing the location, well name, and operator of all wells in the area of review. Include: injection wells, producing wells, plugged wells, abandoned wells, drilling wells, dry holes, and water wells. The plat shall also depict faults, if known or suspected.
6. Attach a description of the needed corrective action on wells penetrating the injection zone in the area of review.
7. Attach a brief description of the proposed injection program.
8. Attach a quantitative analysis from a state-certified laboratory of fresh water from the two nearest fresh water wells. Include legal descriptions.
9. Attach a quantitative analysis from a state-certified laboratory of a representative sample of water to be injected.
10. Attach a list identifying all source wells, including location.
11. Attach a legal description of land ownership within the area of review. List ownership by tract or submit in plat form.
12. Attach an affidavit of mailing certifying that all landowners within the area of review have been notified of the proposed injection well. This notice shall inform the landowners that comments or objections may be submitted to the Commission within 30 days, or that a hearing will be held at which comments or objections may be submitted, whichever is applicable. Include copies of letters sent.
13. Attach all available logging and test data on the well which has not been previously submitted.
14. Attach schematic drawings of the injection system including current well bore construction and proposed well bore and surface facility construction.
15. Attach a Sundry Notice - Form 4 (SFN 5749) detailing the proposed procedure.
16. Read Section 43-02-05-04 of the North Dakota Administrative Code to ensure that this application is complete.
17. The original and two copies of this application and attachments shall be filed with the Industrial Commission of North Dakota, Oil and Gas Division, 600 East Boulevard, Dept. 405, Bismarck, ND 58505-0840.

Exhibit 1 – Lithologic Description

Well:

Buck Shot SWD 5300 31-31
Salt Water Disposal Well
McKenzie County, North Dakota
31-153N-100W

Injection Zone:

Cretaceous Dakota within the Inyan Kara is 450' thick in this area. The section consists of a sequence of alternating sand, silt and shale. Individual sand layers can be up to 50' thick and display a porosity of 20-25%. In the Lindvig 3-14 this section is quite laminated and shows a higher sand percentage toward the base of the section. Sands are generally poorly sorted and vary from fine to coarse grained.

Upper Unit:

The Skull Creek/Newcastle is predominantly medium gray shale and is interbedded with thin layers of siltstone and sandy siltstone. It is about 250' in the Lindvig 3-14 well.

Lower Unit:

The Swift Shale consists of gray shales in the upper portion. These shales become interbedded with limestones and sandy limestones lower in the section. It is 460' in the Lindvig 3-14.

Exhibit 2 - Area of Review Plat



BUCK SHOT SWD 5300 31-31
153N - 100W Section 31
McKenzie County, North Dakota

OASIS PETROLEUM

Exhibit 3 – Proposed Injection Program

June 13, 2012

Buck Shot SWD 5300 31-31
Oasis Petroleum North America, LLC
Section 31, T153N R100W
McKenzie County, North Dakota

Application for Fluid Injection

PROPOSED INJECTION PROGRAM

The Buck Shot SWD 5300 31-31 well will be used to inject produced water from wells in the Indian Hills area - Oasis Bakken and Three Forks wells already on production, in the process of completion, and those soon to be drilled in the four township area of 152-153N and 100-101W into the Dakota formation. Injection depths will be determined after the well is drilled and logged.

The Buck Shot SWD will utilize the existing tanks and pump facilities of the Oasis-operated BWL SWD 5201 11-3. The injection pump will send water to both the BWL SWD and Buck Shot SWD. There will be a pressure transducer at the outlet of the pump that limits the maximum pressure of the discharge to the permitted pressure. This pressure transducer will communicate to the VFD that controls the pump to maximize the efficiency of the pump as well as shut it off at the max allowable pressure. There will be 2 flow meters after the tee in the discharge line, one for the BWL SWD and the other for the Buck Shot SWD.

The flowline to the Buck Shot wellhead will tap into the existing 6 inch flexsteel pipe that is currently in operation for the BWL SWD. This flowline is rated for 2250 psi, approximately 700 psi above the maximum allowable pressure for the Buck Shot SWD. The lease operator will be on location on a daily basis to monitor both SWD locations and the flowline that feeds both the BWL SWD and Buck Shot SWD.

The wellhead and horizontal lateral of the Oasis-operated Lewis Federal 5300 31-31H well is within the ¼ mile area of review but no corrective action is required as the lateral of the Lewis Federal 5300 31-31H is completed within the Bakken Formation which is separated from the Dakota Group by the Swift confining layer and several thousand feet of other impermeable shales.

The proposed Buck Shot SWD is needed to provide a more local disposal facility in the area to reduce costs and ease the burden on regional disposal wells, it will supplement the existing BWL SWD. The anticipated initial injection rate of the well will be 5,000 bwpd at 1,000 psig pressure. However, this rate may increase with additional drilling in the area, subject to the maximum pressure ceiling.

Exhibit 4 - Fresh Water Analysis

ASTRO-CHEM LAB, INC.

4102 2nd Ave. West
Williston, North Dakota 58802-0972
P.O. Box 972
Phone: (701) 572-7355

WATER ANALYSIS REPORT

SAMPLE NUMBER W-12-2438 DATE OF ANALYSIS 3-30-12

COMPANY Oasis Petroleum

CITY Williston STATE ND

WELL NAME AND/OR NUMBER Buckshot SWD

DATE RECEIVED 3-29-12 DST NUMBER

SAMPLE SOURCE Cattle Well (FW Well)

LOCATION NENE OF SEC. 4 TWN. 152 RANGE 101 COUNTY McKenzie

FORMATION DEPTH

DISTRIBUTION Distribution List

RESISTIVITY @ 77°F = 5.400 Ohm-Meters pH = 6.93

SPECIFIC GRAVITY @ 77°F = 1.000 H_2S = Negative

TOTAL DISSOLVED SOLIDS (CALCULATED) = 1855 mg/L (1855 ppm)

SODIUM CHLORIDE (CALCULATED) = 7 mg/L (7 ppm)

CATION	MEQ/L	mg/L	ANION	MEQ/L	mg/L
CALCIUM	5.2	103	CHLORIDE	0.1	4
MAGNESIUM	2.2	24	CARBONATE	0.0	0
SODIUM	16.0	368	BICARBONATE	15.5	946
IRON	0.0	0.1	SULFATE	8.3	400
CHROMIUM	0.0	0.0	NITRATE	0.0	0
BARIUM	0.0	0.0			
POTASSIUM	0.2	9			

WATER ANALYSIS PATTERN



REMARKS Conductivity = 1852 µmhos/cm
Sampled 3-27-12

ANALYZED BY: C. Jungels

Exhibit 4 - Fresh Water Analysis

ASTRO-CHEM LAB, INC.

4102 2nd Ave. West
Williston, North Dakota 58802-0972
P.O. Box 972
Phone: (701) 572-7355

WATER ANALYSIS REPORT

SAMPLE NUMBER W-12-2437 DATE OF ANALYSIS 3-30-12

COMPANY Oasis Petroleum

CITY Williston STATE ND

WELL NAME AND/OR NUMBER Buckshot SWD

DATE RECEIVED 3-29-12 DST NUMBER

SAMPLE SOURCE Wes Lindvig FW Well

LOCATION NESW OF SEC. 3 TWN. 152 RANGE 101 COUNTY McKenzie

FORMATION DEPTH

DISTRIBUTION Distribution List

RESISTIVITY @ 77°F = 8.780 Ohm-Meters pH = 7.33

SPECIFIC GRAVITY @ 77°F = 1.000 H_2S = Negative

TOTAL DISSOLVED SOLIDS (CALCULATED) = 1046 mg/L (1046 ppm)

SODIUM CHLORIDE (CALCULATED) = 24 mg/L (24 ppm)

CATION	MEQ/L	mg/L	ANION	MEQ/L	mg/L
CALCIUM	6.6	131	CHLORIDE	0.4	14
MAGNESIUM	0.8	9	CARBONATE	0.0	0
SODIUM	6.6	152	BICARBONATE	8.2	500
IRON	0.0	0.0	SULFATE	4.9	234
CHROMIUM	0.0	0.0	NITRATE	0.0	0
BARIUM	0.0	0.0			
POTASSIUM	0.2	6			

WATER ANALYSIS PATTERN



REMARKS Conductivity = 1139 µmhos/cm
Sampled 3-27-12

ANALYZED BY: C. Jungels

Exhibit 5 - Source Water Analysis

ASTRO-CHEM LAB, INC.

4102 2nd Ave. West
Williston, North Dakota 58802-0972
P.O. Box 972
Phone: (701) 572-7355

WATER ANALYSIS REPORT

SAMPLE NUMBER W-11-4680 DATE OF ANALYSIS 9-22-11

COMPANY Oasis Petroleum

CITY Williston STATE ND

WELL NAME AND/OR NUMBER Wade 5300 21-30H (API 33-053-03413)

DATE RECEIVED 9-7-11 DST NUMBER

SAMPLE SOURCE P# 20197

LOCATION Lot2 OF SEC. 30 TWN. 153 RANGE 100 COUNTY McKenzie

FORMATION DEPTH

DISTRIBUTION Distribution List

RESISTIVITY @ 77°F = 0.039 Ohm-Meters pH = 5.57

SPECIFIC GRAVITY @ 77°F = 1.205 H_2S = Negative

TOTAL DISSOLVED SOLIDS (CALCULATED) = 308919 mg/L (256364 ppm)

SODIUM CHLORIDE (CALCULATED) = 313165 mg/L (259888 ppm)

CATION	MEQ/L	mg/L	ANION	MEQ/L	mg/L
CALCIUM	1020.0	20237	CHLORIDE	5356.8	189915
MAGNESIUM	120.0	1333	CARBONATE	0.0	0
SODIUM	4010.5	92200	BICARBONATE	2.4	146
IRON	8.8	164.0	SULFATE	4.2	203
CHROMIUM	0.0	0.3	NITRATE	0.0	0
BARIUM	0.6	40.4			
POTASSIUM	119.7	4680			

WATER ANALYSIS PATTERN



REMARKS Sampled 9-7-11

ANALYZED BY: C. Jungels

Exhibit 6 – Preliminary List of Source Wells

Oasis Petroleum North America LLC
Application for Salt Water Disposal
Sec 31-153N-100W, McKenzie County, ND
Buck Shot SWD 5300 31-31

Preliminary List of Source Wells*

Well Name: Angell 5200 31-28H
Operator: Oasis Petroleum North America LLC
Location: NWSW 28-152-100
API Number: #33-053-03077
NDIC Well File: #18437

Well Name: Hysted 5200 44-19H
Operator: Oasis Petroleum North America LLC
Location: SESE 19-152-100
API Number: #33-053-03333
NDIC Well File: #19844

Well Name: Lewis Federal 5300 31-31H
Operator: Oasis Petroleum North America LLC
Location: NWSW 31-153-100
API Number: #33-053-03433
NDIC Well File: #20314

Well Name: Sparrow Federal 5201 42-11H
Operator: Oasis Petroleum North America LLC
Location: SESW 11-152-101
API Number: #33-053-03356
NDIC Well File: #19913

Well Name: Wade Federal 5300 21-30H
Operator: Oasis Petroleum North America LLC
Location: SWNW 30-153-100
API Number: #33-053-03413
NDIC Well File: #20197

**Subject to addition of operated and non-operated source wells.*



BUCK SHOT SWD 5300 31-31
153N - 100W Section 31
McKenzie County, North Dakota

OASIS PETROLEUM

Exhibit 7 - Affidavit of Mailing to Landowners

AFFIDAVIT OF MAILING

State of North Dakota)
)ss
County of McKenzie)

The undersigned, Thomas A. Lenihan, of lawful age, first duly sworn on his oath states that he is a duly authorized agent of Oasis Petroleum America LLC, do hereby certify that I have sent (via certified mail) a Notice of Application for Fluid Injection to each surface owner within a radius of a ¼ mile from the location of the proposed injection well (Buck Shot SWD 5300 31-31), T153NR100W, Section 31: Lot 3, McKenzie County, North Dakota.

The following list contains the names and addresses of all landowners and legal description of the land ownership:

Surface Owners	Legal Description
Wesley G Lindvig 14075 41st Street NW Alexander, ND 58831	Township 153 North, Range 100 West Section 31: Lots 2, 3, 4, E2SW4, SE4NW4 Township 153 North, Range 101 West Section 25: SW4
Michael Haupt ND Dept. of Trust Lands P.O. Box 5523 Bismarck, ND 58506-5523	Township 153 North, Range 101 West Section 36: E2

IN WITNESS WHEREOF, the undersigned has hereunto set his hand this 19th day of June, 2012.

Thomas A. Lenihan

State of North Dakota)
)ss
County of Burleigh)

ACKNOWLEDGMENT INDIVIDUAL

BE IT REMEMBERED, That on this 19th day of June, 2012, before me, a Notary Public, in and for said County and State, personally appeared Thomas A. Lenihan, to me known to be the identical person described in and who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereto set my official signature and affixed my notarial seal, the day and year first above written.

My commission expires: October 25, 2012

Sunne R. Modin Notary Public

SUNNE R. MODIN
Notary Public
State of North Dakota
My Commission Expires Oct. 25, 2012

Exhibit 8 - Copies of Landowner Letters

Sundance Oil & Gas, LLC

June 19, 2012

CERTIFIED MAIL
RETURN-RECEIPT REQUESTED

Michael Haupt
ND Dept. of Trust Lands
P.O. Box 5523
Bismarck, ND 58506-5523

RE: Proposed Saltwater Disposal Well
Buck Shot SWD 5300 31-31
T153N-R100W, Section 31: Lot 3
McKenzie County, North Dakota

Dear Michael:
This letter is to advise you that Oasis Petroleum North America LLC is planning a saltwater disposal well and inject fluids (saltwater) from source wells in the area into the referenced location.

In accordance with the rules and regulations of the North Dakota Industrial Commission ("NDIC"), Oasis is required to give notice that it has made application to perform this work to each landowner within a one-quarter mile radius of the injection site. At a date yet to be determined, the NDIC will conduct a hearing regarding this application in the Department of Mineral Resources Conference Room located at 1016 East Calgary Avenue, Bismarck, ND 58503. Your comments or objections regarding this application may be directed to the Commission at that time.

Written comments or objections may be submitted prior to the hearing to the following address:

North Dakota Industrial Commission
600 E. Boulevard Avenue, Dept. 405
Bismarck, ND 58505

If you have any questions, concerns, or to determine the hearing date, please contact Tom Schumacher, UIC Supervisor for the NDIC Oil & Gas Division at 701-328-8020.

Sincerely,

Thomas A. Lenihan

Thomas A. Lenihan

Sundance Oil & Gas, LLC

June 19, 2012

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Wesley G. Lindvig
14075 41st Street NW
Alexander, ND 58831

RE: Proposed Saltwater Disposal Well
Buck Shot SWD 5300 31-31
T153N-R100W, Section 31: Lot 3
McKenzie County, North Dakota

Dear Wesley:
This letter is to advise you that Oasis Petroleum North America LLC is planning a saltwater disposal well and inject fluids (saltwater) from source wells in the area into the referenced location.

In accordance with the rules and regulations of the North Dakota Industrial Commission ("NDIC"), Oasis is required to give notice that it has made application to perform this work to each landowner within a one-quarter mile radius of the injection site. At a date yet to be determined, the NDIC will conduct a hearing regarding this application in the Department of Mineral Resources Conference Room located at 1016 East Calgary Avenue, Bismarck, ND 58503. Your comments or objections regarding this application may be directed to the Commission at that time.

Written comments or objections may be submitted prior to the hearing to the following address:

North Dakota Industrial Commission
600 E. Boulevard Avenue, Dept. 405
Bismarck, ND 58505

If you have any questions, concerns, or to determine the hearing date, please contact Tom Schumacher, UIC Supervisor for the NDIC Oil & Gas Division at 701-328-8020.

Sincerely,

Thomas A. Lenihan

Thomas A. Lenihan

PO Box 2631 • Bismarck, ND 58502 • Phone 701-258-1827 • Fax 701-224-1153 • E-mail server@sundanceoil.com

Buck Shot SWD 5300 31-31
WELLBORE SCHEMATIC

API #:
FORMATION: Dakota
FIELD: Camp



OASIS PETROLEUM INC.

Buck Shot SWD 5300 31-31 T153N-R100W Sec. 31 1710' FSL & 1125' FWL	Status: Planned McKenzie County, North Dakota Updated: 08/14/2012

Exhibit 9 - Surface Facilities Diagram

Buck Shot SWD 5300 31-31
Oasis Petroleum
Section 31, T153N R100W
McKenzie County, North Dakota






BWL SWD 5201 11-3
Oasis Petroleum
Site Layout
+/- 518'
+/- 350'
Truck Lane #1
Truck Lane #2
Approx. 4.09 acres
Truck Unloading Station #2
Truck Unloading Station #1
+/- 25'
+/- 50'
Match West edge of location to existing lease road
Primary Dike
Containment = 7,266 bbl
Effective Containment = 6,412 bbl
(less footprints of tanks and pump shack)
SWD Facility
3000 bbl
3000 bbl
DIKE: 170' L x 80' W x 3'H
+/- 35' W
+/- 35" W
EX. CATTLE GUARD
+/- 500'
EX. FENCE
Secondary Dike
Containment = 62,344 bbl
(2' berm around entire location)
EX. GRAVEL ROAD

SUNDRY NOTICES AND REPORTS ON WELLS - FORM 4

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 5749 (09-2006)

Well File No. 90244

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

- ☑ Notice of Intent — Approximate Start Date: **September 1, 2012**
- ☐ Report of Work Done — Date Work Completed:
- ☐ Notice of Intent to Begin a Workover Project that may Qualify for a Tax Exemption Pursuant to NDCC Section 57-51.1-03. — Approximate Start Date:

☐ Drilling Prognosis	☐ Spill Report
☐ Redrilling or Repair	☐ Shooting
☐ Casing or Liner	☐ Acidizing
☐ Plug Well	☐ Fracture Treatment
☐ Supplemental History	☐ Change Production Method
☐ Temporarily Abandon	☐ Reclamation
☑ Other **Completion of injection well**	

Well Name and Number					
Buck Shot SWD 5300 31-31					
Footages		Qtr-Qtr	Section	Township	Range
1710 F **S** L	**1125** F **W** L	**NWSW**	**31**	**153 N**	**100 W**
Field		Pool		County	
Camp		**Dakota**		**McKenzie**	

24-HOUR PRODUCTION RATE

Before		After	
Oil	Bbls	Oil	Bbls
Water	Bbls	Water	Bbls
Gas	MCF	Gas	MCF

Name of Contractor(s)			
Address	City	State	Zip Code

DETAILS OF WORK

1. **Notify state inspector 24 hours before commencing operations.**
2. **Rig up pump truck and test wellbore to 1,500 psi.**
3. **MIRU wireline and mast truck.**
4. **RIH with perf assembly and perforate Dakota at 6 spf.**
5. **Rig up pump truck and perform injectivity test. If necessary, acidize perforations and add additional perfs.**
6. **PU plastic lined packer and new 4.5" plastic coated tubing. TIH and set packer 50' above top perforation.**
7. **Pressure test the backside to 1,000 psi and record - MIT must be witnessed by a NDIC Field Inspector.**
8. **RD workover rig and install SWD facilities.**

Company			Telephone Number
Oasis Petroleum			**(281) 404-9500**
Address			
1001 Fannin, Suite 1500			
City		State	Zip Code
Houston		**TX**	**77002**
Signature	Printed Name		
[signature]	**Tommy Thompson**		
Title	Date		
Sr Facilities Engineer	**August 14, 2012**		
Email Address			
tthompson@oasispetroleum.com			

FOR STATE USE ONLY

☐ Received	☒ Approved
Date 9-5-2012	
By [signature]	
Title UNDERGROUND INJECTION SUPERVISOR	

September 5, 2012

Brandi Terry
Regulatory Specialist
OASIS PETROLEUM NORTH AMERICA LLC
1001 Fannin Suite 1500
Houston, TX 77002

RE: VERTICAL WELL
BUCK SHOT SWD 5300 31-31
NWSW Section 31-153N-100W
McKenzie County
Well File # 90244

Dear Brandi :

Pursuant to Commission Order No. 20523, approval to drill the above captioned well is hereby given.

PERMIT STIPULATIONS: OASIS PETRO NO AMER must contact NDIC Field Inspector Richard Dunn at 701-7703-554 prior to location construction.

Drilling pit

NDAC 43-02-03-19.4 states that "a pit may be utilized to bury drill cuttings and solids generated during well drilling and completion operations, providing the pit can be constructed, used and reclaimed in a manner that will prevent pollution of the land surface and freshwaters. Reserve and circulation of mud system through earthen pits are prohibited. All pits shall be inspected by an authorized representative of the director prior to lining and use. Drill cuttings and solids must be stabilized in a manner approved by the director prior to placement in a cuttings pit."

Location Construction Commencement (Three Day Waiting Period)

Operators shall not commence operations on a drill site until the 3rd business day following publication of the approved drilling permit on the NDIC - OGD Daily Activity Report. If circumstances require operations to commence before the 3rd business day following publication on the Daily Activity Report, the waiting period may be waived by the Director. Application for a waiver must be by sworn affidavit providing the information necessary to evaluate the extenuating circumstances, the factors of NDAC 43-02-03-16.2 (1), (a)-(f), and any other information that would allow the Director to conclude that in the event another owner seeks revocation of the drilling permit, the applicant should retain the permit.

Permit Fee & Notification

Payment was received in the amount of $100 via credit card .The permit fee has been received. It is requested that notification be given immediately upon the spudding of the well. This information should be relayed to the Oil & Gas Division, Bismarck, via telephone. The following information must be included: Well name, legal location, permit number, drilling contractor, company representative, date and time of spudding. Office hours are 8:00 a.m. to 12:00 p.m. and 1:00 p.m. to 5:00 p.m. Central Time. Our telephone number is (701) 328-8020, leave a message if after hours or on the weekend.

Surface casing cement

Tail cement utilized on surface casing must have a minimum compressive strength of 500 psi within 12 hours, and tail cement utilized on production casing must have a minimum compressive strength of 500 psi before drilling the plug or initiating tests.

Logs

NDAC Section 43-02-03-31 requires the running of (1) a suite of open hole logs from which formation tops and porosity zones can be determined, (2) a Gamma Ray Log run from total depth to ground level elevation of the well bore, and (3) a log from which the presence and quality of cement can be determined (Standard CBL or Ultrasonic cement evaluation log) in every well in which production or intermediate casing has been set, this log must be run prior to completing the well. All logs run must be submitted free of charge, as one digital TIFF (tagged image file format) copy and one digital LAS (log ASCII) formatted copy. Digital logs may be submitted on a standard CD, DVD, or attached to an email sent to digitallogs@nd.gov Thank you for your cooperation.

Sincerely,

Stephen Fried
UIC Supervisor

APPLICATION FOR PERMIT TO DRILL - FORM 1

INDUSTRIAL COMMISSION OF NORTH DAKOTA
OIL AND GAS DIVISION
600 EAST BOULEVARD DEPT 405
BISMARCK, ND 58505-0840
SFN 4615 (03-2006)

PLEASE READ INSTRUCTIONS BEFORE FILLING OUT FORM.
PLEASE SUBMIT THE ORIGINAL AND ONE COPY.

Type of Work	Type of Well	Approximate Date Work Will Start	Confidential Status
New Location	Oil & Gas	09 / 15 / 2012	No

Operator	Telephone Number
OASIS PETROLEUM NORTH AMERICA LLC	(281) 404-9491

Address	City	State	Zip Code
1001 Fannin Suite 1500	Houston	TX	77002

Name of Surface Owner or Tenant
Wesley G Lindvig

Address	City	State	Zip Code
14075 41st St NW	Williston	ND	58801

WELL INFORMATION

☑ Notice has been provided to the owner of any permanently occupied dwelling within 1,320 feet.

☑ This well is not located within five hundred feet of an occupied dwelling.

Well Name	Well Number
BUCK SHOT SWD	5300 31-31

	Location	Qtr-Qtr	Section	Township	Range	County
At Surface	1710 F S L 1125 F W L	NWSW	31	153 N	100 W	McKenzie
If Directional, Top of Pay	F L F L			N	W	
Proposed Bottom Hole Location	F L F L			N	W	

Latitude of Well Head	Longitude of Well Head	NAD Reference	Description of (Subject to NDIC Approval)
48 ° 1 ' 44.70 "	-103 ° 35 ' 58.47 "	WGS84	

Ground Elevation	Acres in Spacing/Drilling Unit	Spacing/Drilling Unit Setback Requirement	Industrial Commission Order
2160 Feet Above S.L.		Feet	

Objective Horizons	Pierre Shale Top
Dakota	2022

Proposed Surface Casing	Size	Weight	Depth	Cement Volume	
	9 - 5/8 "	36 Lb./Ft.	2135 Feet	673 Sacks	**NOTE: Surface hole must be drilled with fresh water and surface casing must be cemented back to surface.**

Proposed Longstring Casing	Size	Weight(s)	Longstring Total Depth	Cement Volume	Cement Top	Top Dakota Sand
	7 - "	26 Lb./Ft.	5965 Feet MD 5965 Feet TVD	440 Sacks	2135 Feet	5462 Feet

Base Last Charles Salt (If Applicable)	Estimated Total Depth (feet)	Drilling Mud Type (Vertical Hole - Below Surface Casing)
Feet	5965 Feet MD 5965 Feet TVD	Fresh Water

Proposed Logs
OH LOGS: Triple Combo to Dakota GR/RES to BSC GR-Surf CBLGR-TOC/GR-BSC

Comments

I hereby swear or affirm that the information provided is true, complete and correct as determined from all available records.	Date 08 / 21 / 2012

	Printed Name	Title
ePermit	Brandi Terry	Regulatory Specialist

FOR STATE USE ONLY

Permit and File Number	API Number
90244	33 - 053 - 90244
Field: BAKER	
Pool: DAKOTA	Permit Type: SALT WATER DISPOSAL

FOR STATE USE ONLY

Date Approved
9 / 5 / 2012
By: Stephen Fried
Title: UIC Supervisor

REQUIRED ATTACHMENTS: Certified surveyors plat, estimated geological tops, proposed mud/cementing plans, $100 fee.

WELL LOCATION PLAT

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



VICINITY MAP



STAKED ON 3/16/12
VERTICAL CONTROL DATUM WAS BASED UPON CONTROL POINT 50 WITH AN ELEVATION OF 2164.3'

THIS SURVEY AND PLAT IS BEING PROVIDED AT THE REQUEST OF FABIAN KJORSTAD OF OASIS PETROLEUM. I CERTIFY THAT THIS PLAT CORRECTLY REPRESENTS WORK PERFORMED BY ME OR UNDER MY SUPERVISION AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

DARYL D. KASEMAN LS-3880

REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS-3880
DATE: 4/5/12
NORTH DAKOTA

1/7
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
WELL LOCATION PLAT
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description

Oasis Petroleum
Well Summary
Buck Shot SWD 5300 31-31
Section 31 T153N R100W
McKenzie County, ND

SURFACE CASING AND CEMENT DESIGN

							Make-up Torque (ft-lbs)		
Size	**Interval**	**Weight**	**Grade**	**Coupling**	**I.D.**	**Drift**	**Minimum**	**Optimum**	**Max**
9-5/8"	0' to 2,125'	36	J-55	LTC	8.921"	8.765"	3400	4530	5660

Interval	Description	Collapse	Burst	Tension	Cost per ft
		(psi) a	(psi) b	(1000 lbs) c	
0' to 2,125'	9-5/8", 36#, J-55, LTC, 8rd	2020 / 1.98	3520 / 3.46	453 / 2.73	

API Rating & Safety Factor

a) Based on full casing evacuation with 9.2 ppg fluid on backside (2,125' setting depth).
b) Burst pressure based on 9.2 ppg fluid with no fluid on backside (2,125' setting depth).
c) Based on string weight in 9.2 ppg fluid at 2,125' TVD plus 100k# overpull. (Buoyed weight equals 66k lbs.)

Cement volumes are based on 9-5/8" casing set in 13-1/2" hole with 55% excess to circulate cement back to surface. Mix and pump the following slurry.

Pre-flush (Spacer): **20 bbls** fresh water

Lead Slurry: **441 sks** (233 bbls) 11.5 lb/gal conventional system with 94 lb/sk cement, 4% extender, 2% expanding agent, 2% CaCl2 and 0.125 lb/sk lost circulation control agent

Tail Slurry: **225 sks** (60 bbls) 15.8 lb/gal conventional system with 94 lb/sk cement, 1% CaCl, and 0.125 lb/sk lost circulation control agent

Oasis Petroleum
Well Summary
Buck Shot SWD 5300 31-31
Section 31 T153N R100W
McKenzie County, ND

INTERMEDIATE CASING AND CEMENT DESIGN

							Make-up Torque (ft-lbs)		
Size	**Interval**	**Weight**	**Grade**	**Coupling**	**I.D.**	**Drift**	**Minimum**	**Optimum**	**Max**
7"	0' to 5,965'	26	L-80	LTC	6.276"	6.151"	3900	4900	5900

Interval	Description	Collapse	Burst	Tension	Cost per ft
		(psi) a	(psi) b	(1000 lbs) c	
0' to 5,965'	7", 26#, L-80, LTC, 8rd	5410 / 1.74	7240 / 1.36	511 / 2.00	

API Rating & Safety Factor

a) Collapse pressure based on full casing evacuation with 10 ppg fluid on backside (5,965' setting depth).
b) Burst pressure based on 5,000 psi max stimulation pressure plus 10.0 ppg fluid inside casing with 9.0 ppg fluid on backside (5,965' setting depth).
c) Based on string weight in 10 ppg fluid at 5,965' TVD plus 100k# overpull. (Buoyed weight equals 131k lbs.)

Cement volumes are based on 7" casing set in 8-3/4" hole with 30% excess. Estimated TOC @ 2,125'. Mix and pump the following slurry.

Pre-flush (Spacer): **150 bbls** Saltwater
20 bbls CW8 System
20 bbls fresh water

Lead Slurry: **180 sks** (83 bbls) 11.5 lb/gal LiteCRETE with 27.005 lb/sk Extender, 10% NaCl, 0.40% Dispersant, 0.25% Retarder, 0.20% Anti-foam, 0.10% Retarder, 0.25 lb/sk lost circulation control agent

Tail Slurry: **260 sks** (158 bbls) 15.6 lb/gal conventional system with 94 lb/sk cement, 10% NaCl, 35% Silica, 0.20% dispersant, 0.40% fluid loss agent, 0.10% retarder, and 0.25 lb/sk lost circulation control agent

DRILLING PLAN

PROSPECT/FIELD	0 **Vertical Dakota Water Disposal Well**	**COUNTY/STATE**	McKenzie Co., ND
OPERATOR	Oasis Petroleum	**RIG**	TBD
WELL NAME	Buck Shot SWD 5300 31-31		
LOCATION	NWSW 31-153N-100W Surface Location (survey plat): 1710' fsl	1125' fwl	
EST. T.D.	5,965	**GROUND ELEV:**	2157 Finished Pad Elev. **Sub Hieght:** 15
		KB ELEV:	2172

PROGNOSIS: Based on 2,172' KB(est)

MARKER	**DEPTH (Surf Loc)**	**DATUM (Surf Loc)**
Pierre	2,022	150
Greenhorn	4,629	(2,457)
Mowry	5,044	(2,872)
Dakota Top	5,462	(3,290)
First Dakota Sand Top	5,516	(3,344)
First Dakota Sand Base	5,549	(3,377)
Second Dakota Sand Top	5,670	(3,498)
Second Dakota Sand Base	5,757	(3,585)
Third Dakota Sand Top	5,795	(3,623)
Third Dakota Sand Base	5,815	(3,643)
Forth Dakota Sand Top	5,837	(3,665)
Forth Dakota Sand Base	5,915	(3,743)

LOGS: **Type** / **Interval**

OH Logs: Triple Combo up to casing, GR/Res to BSC; GR to surf

CBL/GR: Above top of cement/GR to base of casing

DEVIATION: None

DST'S: None planned

CORES: None planned

MUDLOGGING: None planned

BOP: 3k blind, pipe & annular

Max. Anticipated BHP: 2947

Surface Formation: *Glacial till*

MUD:	**Interval**		**Type**	**WT**	**Vis**	**WL**	**Remarks**
Surface	0' -	2,125'	FW/Gel Lime Sweeps	8.6 - 8.9	28-34	NC	Circ Mud Tanks
Straight Hole	2,125' -	#REF!	Invert	8.8-9.5	40-60	HTHP	Circ Mud Tanks

CASING:	**Size**	**Wt ppf**	**Hole**	**Depth**	**Cement**	**WOC**	**Remarks**
Surface:	9 5/8"	36	13 1/2"	2,125	To surface	12 hours	
Intermediate:	7"	26	8 3/4"	5,965	2,125	12 hours	

PROBABLE PLUGS, IF REQ'D:

OTHER:	**MD**	**TVD**	**FNL/FSL**	**FEL/FWL**	**S-T-R**	**AZI**
Surface:	2,125	2,125	298' FNL	291' FWL	**T152N-R101W-Sec. 3**	N/A
Csg Pt/TD:	5,965	5,965	298' FNL	291' FWL	**T152N-R101W-Sec. 3**	N/A

Comments:

MWD survey every 100'
Drill to TD and log

Reserve pit fluids will be hauled to the nearest disposal site/Reserve pit solids will be solidified and reclaimed in the lined reserve pit

OASIS PETROLEUM

Geology: ANELSON 06-12-2012 **Engineering:** M Brown 6/13/2012

Oasis

Indian Hills
153N-100W-31
Buck Shot SWD 5300 31-31

OH

Plan: Plan #1

Standard Planning Report

13 June, 2012

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	WELL @ 2172.0ft (Original Well Elev)
Project:	Indian Hills	**MD Reference:**	WELL @ 2172.0ft (Original Well Elev)
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	Plan #1		

Project Indian Hills

Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	North Dakota Northern Zone		

Site 153N-100W-31

Site Position:		**Northing:**	119,066.39 m	**Latitude:**	48° 1' 44.700 N
From:	Lat/Long	**Easting:**	368,900.31 m	**Longitude:**	103° 35' 58.470 W
Position Uncertainty:	0.0 ft	**Slot Radius:**	13.200 in	**Grid Convergence:**	-2.31 °

Well Buck Shot SWD 5300 31-31

Well Position	**+N/-S**	0.0 ft	**Northing:**	119,066.39 m	**Latitude:**	48° 1' 44.700 N
	+E/-W	0.0 ft	**Easting:**	368,900.31 m	**Longitude:**	103° 35' 58.470 W
Position Uncertainty		0.0 ft	**Wellhead Elevation:**		**Ground Level:**	2,157.0 ft

Wellbore OH

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	6/12/2012	8.46	73.03	56,652

Design Plan #1

Audit Notes:

Version: **Phase:** PROTOTYPE **Tie On Depth:** 0.0

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.0	0.0	0.0	0.00

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,965.0	0.00	0.00	5,965.0	0.0	0.0	0.00	0.00	0.00	0.00	

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	WELL @ 2172.0ft (Original Well Elev)
Project:	Indian Hills	**MD Reference:**	WELL @ 2172.0ft (Original Well Elev)
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	Plan #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
2,022.0	0.00	0.00	2,022.0	0.0	0.0	0.0	0.00	0.00	0.00
Pierre									
2,125.0	0.00	0.00	2,125.0	0.0	0.0	0.0	0.00	0.00	0.00
9 5/8"									
4,629.0	0.00	0.00	4,629.0	0.0	0.0	0.0	0.00	0.00	0.00
Greenhorn									
5,044.0	0.00	0.00	5,044.0	0.0	0.0	0.0	0.00	0.00	0.00
Mowry									
5,462.0	0.00	0.00	5,462.0	0.0	0.0	0.0	0.00	0.00	0.00
Dakota Top									
5,516.0	0.00	0.00	5,516.0	0.0	0.0	0.0	0.00	0.00	0.00
First Dakota Sand Top									
5,549.0	0.00	0.00	5,549.0	0.0	0.0	0.0	0.00	0.00	0.00
First Dakota Sand Base									
5,670.0	0.00	0.00	5,670.0	0.0	0.0	0.0	0.00	0.00	0.00
Second Dakota Sand Top									
5,757.0	0.00	0.00	5,757.0	0.0	0.0	0.0	0.00	0.00	0.00
Second Dakota Sand Base									
5,795.0	0.00	0.00	5,795.0	0.0	0.0	0.0	0.00	0.00	0.00
Third Dakota Sand Top									
5,815.0	0.00	0.00	5,815.0	0.0	0.0	0.0	0.00	0.00	0.00
Third Dakota Sand Base									
5,837.0	0.00	0.00	5,837.0	0.0	0.0	0.0	0.00	0.00	0.00
Forth Dakota Sand Top									
5,915.0	0.00	0.00	5,915.0	0.0	0.0	0.0	0.00	0.00	0.00
Forth Dakota Sand Base									
5,965.0	0.00	0.00	5,965.0	0.0	0.0	0.0	0.00	0.00	0.00
TD at 5965.0 - 7"									

Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
2,125.0	2,125.0	9 5/8"	9.625	13.500
5,965.0	5,965.0	7"	7.000	8.750

Database:	OpenWellsCompass - EDM Prod	**Local Co-ordinate Reference:**	Well Buck Shot SWD 5300 31-31
Company:	Oasis	**TVD Reference:**	WELL @ 2172.0ft (Original Well Elev)
Project:	Indian Hills	**MD Reference:**	WELL @ 2172.0ft (Original Well Elev)
Site:	153N-100W-31	**North Reference:**	True
Well:	Buck Shot SWD 5300 31-31	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	Plan #1		

Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
2,022.0	2,168.0	Pierre			
4,629.0	4,775.0	Greenhorn			
5,044.0	5,190.0	Mowry			
5,462.0	5,608.0	Dakota Top			
5,516.0	5,662.0	First Dakota Sand Top			
5,549.0	5,695.0	First Dakota Sand Base			
5,670.0	5,816.0	Second Dakota Sand Top			
5,757.0	5,903.0	Second Dakota Sand Base			
5,795.0	5,941.0	Third Dakota Sand Top			
5,815.0	5,961.0	Third Dakota Sand Base			
5,837.0	5,983.0	Forth Dakota Sand Top			
5,915.0	6,061.0	Forth Dakota Sand Base			

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	Local Coordinates +E/-W (ft)	Comment
5,965.0	5,965.0	0.0	0.0	TD at 5965.0

PAD LAYOUT

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS-3880
DATE: 4/5/12
NORTH DAKOTA

THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 4/5/12 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

NOTE: All utilities shown are preliminary only, a complete utilities location is recommended before construction.

Revision No.	Date	By	Description

OASIS PETROLEUM NORTH AMERICA, LLC
PAD LAYOUT
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By: B.H.H. Project No.: S12-09-068
Checked By: D.D.K. Date: APRIL 2012

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

INTERSTATE ENGINEERING
Professionals you need, people you trust

SHEET NO. 2/7

ACCESS APPROACH

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 4/5/12 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.

NOTE: All utilities shown are preliminary only, a complete utilities location is recommended before construction.

3/7
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
ACCESS APPROACH
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description



4/7
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
QUAD LOCATION MAP
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description

COUNTY ROAD MAP

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



SCALE: 1" = 2 MILE

5/7
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
COUNTY ROAD MAP
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description

CROSS SECTIONS

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT SWD 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA



STA. 2+50

THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY DARYL D. KASEMAN, PLS, REGISTRATION NUMBER 3880 ON 4/5/12 AND THE ORIGINAL DOCUMENTS ARE STORED AT THE OFFICES OF INTERSTATE ENGINEERING, INC.



STA. 2+00

REGISTERED LAND SURVEYOR
DARYL D. KASEMAN
LS-3880
DATE: 4/5/12
NORTH DAKOTA



STA. 1+00



STA. 0+00

SCALE
HORIZ 1"=80'
VERT 1"=20'

6/7
SHEET NO.

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM NORTH AMERICA, LLC
PAD CROSS SECTIONS
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description

WELL LOCATION SITE QUANTITIES

OASIS PETROLEUM NORTH AMERICA, LLC
1001 FANNIN, SUITE 1500, HOUSTON, TX 77002
"BUCK SHOT 5300 31-31"
1710 FEET FROM SOUTH LINE AND 1125 FEET FROM WEST LINE
SECTION 31, T153N, R100W, 5TH P.M., MCKENZIE COUNTY, NORTH DAKOTA

WELL SITE ELEVATION	2159.9
WELL PAD ELEVATION	2157.0

EXCAVATION	4,877
PLUS PIT	3,150
	8,027
EMBANKMENT	1,285
PLUS SHRINKAGE (15%)	386
	1,671
STOCKPILE PIT	3,150
STOCKPILE TOP SOIL (6")	1,302
STOCKPILE MATERIAL	1,904
DISTURBED AREA FROM PAD	1.61 ACRES

NOTE: ALL QUANTITIES ARE IN CUBIC YARDS (UNLESS NOTED)
CUT END SLOPES AT 2:1
FILL END SLOPES AT 3:1

WELL SITE LOCATION
1710' FSL
1125' FWL

INTERSTATE ENGINEERING
Professionals you need, people you trust

Interstate Engineering, Inc.
P.O. Box 648
425 East Main Street
Sidney, Montana 59270
Ph (406) 433-5617
Fax (406) 433-5618
www.iengi.com
Other offices in Minnesota, North Dakota and South Dakota

OASIS PETROLEUM, LLC
QUANTITIES
SECTION 31, T153N, R100W
MCKENZIE COUNTY, NORTH DAKOTA

Drawn By:	B.H.H.	Project No.:	S12-09-068
Checked By:	D.D.K.	Date:	APRIL 2012

Revision No.	Date	By	Description